APPENDIX SEVEN

Waipā Catchment Project Assessments

Contents

Waipā River erosion protection and remediation – Pirongia to Ngāruawāhia
Walkway from Te Kōwhai to Ngāruawāhia township via Te Otamanui gully and along Waipā River 12
Enhancement of Waipā wetlands in priority nutrient catchments (Waikato district)
Kaniwhaniwha catchment erosion protection and remediation27
Kaniwhaniwha catchment streams fish habitat rehabilitation and restoration of forest remnants 34
Enhancement of Waipā wetlands in priority nutrient catchments (Waipā district)45
Restoration of priority lowland kahikatea remnants (and associated wetlands) between Te Kūiti and Templeview
Enhancement of water levels in the Moanatuatua Wetland61
Mangakara Stream fish habitat rehabilitation66
Mangauika Stream fish habitat rehabilitation71
Waipā River bank erosion protection and remediation – Ōtorohanga to Pirongia77
Tuna habitat rehabilitation within 7 Pūniu River oxbows84
Ngakoaohia Stream (and selected tributaries) fish habitat rehabilitation90
Moakurarua integrated catchment programme95
Tuna habitat rehabilitation within 10 Waipā River oxbows105
Mangatutu River erosion protection, remediation and management and fish habitat rehabilitation
Waitomo River – headwaters to caves catchment erosion protection and remediation
Rehabilitation of fish habitat at Ōtorohanga (Waipā River)129
Waipā River bank erosion protection and remediation – Toa Bridge to Ōtorohanga134
Upper Pūniu catchment erosion protection and remediation143
Mangapū River erosion protection and riparian enhancement147
Biodiversity restoration within lowland kahikatea fragments in the Mangapū catchment
Mangaokewa Stream erosion protection and remediation159
Mangarapa catchment erosion protection and remediation165
Mangatea catchment erosion protection and remediation172
Mangarama catchment erosion protection and remediation
Biodiversity restoration of priority sites in the upper Waipā catchment182

WP 1	Waipā River erosion protection and remediation -	
Priority: High	Pirongia to Ngāruawāhia	BCR value
Relevant unit goal(s)	River margins prone to significant erosion are managed to minimise erosion risk, whilst enhancing aquatic habitat and retaining the natural character of river systems.	Ben value
	Riparian planting of preferably indigenous species is undertaken to stabilise riverbanks, reduce erosion and enhance terrestrial and aquatic biodiversity.	
	Water quality is such that waters within the catchment are swimmable and safe to take food from in all places.	
Name of feature	Waipā River – Pirongia to Ngāruawāhia	
Brief description of feature	This reach consists of 30km of Waipā main stem from Pirongia to Whatawhata and 28km from the Whatawhata bridge to the confluence with the Waikato River at Ngāruawāhia. The river here is well incised with some bank slumping in areas. Margins are not fully fenced and lack continuous vegetation. There is increased incidence of bank collapse following high flow events, especially where there is a lack of stabilising vegetation. Pest willow species are throughout the extent of this reach.	
	This stretch of the Waipā provides a pathway for patupaiarehe, or spiritual beings, who travel between various maunga along the Waipā to Taupiri and other significant areas. There are historic pā sites along the margins such as Tangirau and Moehaki. Taniwha also traverse the Waipā and have resting places along its banks. The Waipā is also a main stem of travel for significant fisheries and tribes.	
	Based on regular monitoring undertaken by Waikato Regional Council, the Waipā River along this stretch (at Whatawhata Bridge) is not safe for swimming due to unsatisfactory levels of E. coli. Clarity, TN and TP are also considered unsatisfactory.	
Desired state to achieve the Vision & Strategy	 A 58km stretch of river with stable, vegetated banks and where major erosion events are limited. A riparian margin at least 10 metres wide that is well vegetated with native plants and exotic plants where required to prevent erosion. The river is swimmable, fishable and has access for recreation. Iwi and community have a strong connection to the river and are active in its use protection and restoration. 	
Impact on Vision & Strategy	In a restored condition the Waipā River – Pirongia to Ngāruawāhia reach – would have a very high impact on	VS = 350

	giving effect to the V level.		
Key threats to the feature that this	Key threat	Impact on feature	
project addresses	Mass bank erosion events and ongoing bank scouring	Estimated to yield approximately 25,000 tonnes sediment per year to the Waipā River and lower Waikato River.	
Project goal/s	 The river has stabl vegetated (native margin along the r Stock is excluded f is set back at least 	oject commencement: e banks and a continuous and exotic for erosion control) 58km each from Pirongia to Ngāruawāhia. from 100% of the river and new fencing 15m from the riverbank. /aipā River over this stretch is reduced	
Priority works for funding	Suggested works cou organisation or priva	Id be implemented either by an te citizens (using contractors or their oject could be undertaken as a whole, r components.	
	 Based on surveys of assuming that all u it is estimated that along this reach of setback at least 15 (5-wire, 2 electric a \$426,880. Pole planting for b required over 22kr planted every 10m equates to 2200 pc It is estimated that planting which equites to be will be weedy and 	t 75% of the margin will require new uates to 112ha of native planting. Cost \$4,429,824. This assumes that sites require weed control prior to planting.	
	Staff to carry out land Health and Safety red inspect works, manag fencing or planting), management. Incide overheads, consumal fees.	t/staffing/incidentals downer liaison, iwi engagement, quirements, negotiate agreements, ge parts of the work as required (e.g. project reporting and financial entals include transport, office bles and miscellaneous professional	
Time lag for benefits to be realised	If works were implen	be 25% of the direct project costs. Thented at an even pace over a 15-year d that the majority of the project	L = 13.5

	benefits would be seen approximately 13-14 years after	
	project commencement.	
Effectiveness of works	The Waipā River (Pirongia to Ngāruawāhia) is currently in poor condition with few of the Vision & Strategy desired state aspects being met. The river is not swimmable, the banks are unstable in many places and stock have access to the river at a number of locations. The riverbanks are not well vegetated with native plants. Some deterioration in the river is expected over the next 20 years in the absence of this project, with impacts of the upper catchment and bank stability in the Waipā main stem likely to lead to further decline in water quality and habitat for fish. This decline is expected to be offset by the outcomes of this project which will improve aspects related to bank stability, stock exclusion and extent of native vegetation along the margins. Secondary benefits in E. coli reduction, fish habitat and biodiversity can also be expected. Overall, however, the upper catchment impacts will still be the biggest factor in water quality through this reach and it is acknowledged that achieving the Vision & Strategy desired state will take longer than the 20 year horizon used for the	W = 0.05
Risk of technical	purposes of the Restoration Strategy. There is a moderate risk of project failure due to technical	F = 0.82
failure	feasibility. Risks are mostly related to establishment of plantings or loss of works due to flooding and/or erosion before they are established. This would be minimised by the fencing setbacks being at least 15m and by planting sterile willow poles to stabilise banks while native plantings establish.	
Adoptability	It is estimated that almost half of landowners would adopt the works if they were fully incentivised. The extent of the fencing setbacks may be a challenge in terms of uptake, however, there are some existing projects along this reach that provide a good example of what can be achieved with larger riparian margins.	A = 0.45
Information quality	Average – estimates are based on aerial photographs, Waipā catchment riparian surveys and input from catchment officers who are familiar with the reach and are working with landowners to help them undertake similar works.	
Knowledge gaps and response	Unknown specifically how much fencing already exists. This would need to be established as part of the project planning.	
Socio-political risks	Low risk that the project will fail to meet its goals over the long term due to socio-political risks.	P = 0.85
Project duration (years)	15 years	

Up-front cost – total			C = 6.11
for implementation phase/project duration	Task	Cost	
	Native planting (112ha)	4,429,824	
	Poplar/willow poles (2200)	30,800	
	Fencing (53km)	426,880	
	Project management/staffing/incidentals (25%)	1,221,876	
	Total	\$6,109,380	







Waipā River at Pirongia showing eroding and mostly devegetated banks where stock have access to the river. This project proposes that a priority for funding would be fencing and planting of this margin.



Example of devegetated banks of Lower Waipā main stem.



Waipā River erosion prone banks.



Lower Waipā main stem with example of plantings.

WP 2	Walkway from Te Kōwhai to Ngāruawāhia township via Te	
Priority: High	Otamanui gully and along Waipā River	BCR value
Relevant unit goal(s)	The river provides for recreational use and social needs, is widely used by the community, and is a place to gather kai, relax, plan and exercise.	
Name of feature	Waipā River Te Kōwhai to Ngāruawāhia and Te Otamanui Lagoon and gully	
Brief description of feature	This feature includes the Te Otamanui gully ecosystem between Te Kōwhai Village and the Waipā River (in the vicinity of Bedford Road) and a 5.3km section of the lower Waipā River from the Te Otamanui Stream inflow downstream to Ngāruawāhia township.	
	The upstream section of the gully ecosystem comprises predominantly willow wetland and the Te Otamanui Stream with small pockets of remnant and planted native vegetation. The stream flows into the Te Otamanui Lagoon in the lower reaches and enters the Waipā River at Bedford Road.	
	The lower reach of the gully has pockets of remnant and planted native vegetation (e.g. kahikatea and cabbage trees). A partially completed walkway extends along the true right bank of the gully and the Te Otamanui community group has carried out native planting along the completed sections of walkway.	
	The lagoon exits to the Waipā where an historic papakāinga (settlement) was situated known as Kaitarakihi. This signals the importance of the area for providing food to the people of the area.	
	The 5.3km section of Waipā River is fenced to exclude stock in most places and predominantly vegetated with a narrow margin of willow trees.	
	There is opportunity to increase the recreation opportunities within the gully ecosystem and along the river by extending Te Otamanui walkway along the Waipā River to Ngāruawāhia township.	
Desired state to achieve the Vision & Strategy	 Stock is excluded from the Waipā River and Te Otamanui Stream and gully. Waterways have well vegetated riparian margins that provides erosion protection, shade and shelter. 	
	 Native fish are abundant and there is a wide diversity of species present. The waterways are swimmable, fishable and have access for recreation. Iwi and communities have a strong connection to the waterways and are active in their use, protection and restoration. 	
Impact on Vision & Strategy	In a restored condition, the Waipā River from Te Kōwhai to Ngāruawāhia and Te Otamanui Lagoon would have a high impact on giving effect to the Vision & Strategy at a Waipā catchment level.	VS = 40

Key threats to			
the feature that	Key threat	Impact on the asset	
this project addresses	People become disconnected from the waterways and see the area more as a resource than something that needs to be nurtured and cared for.	The opportunity for people to access, recreate and connect with the waterways are not realised.	
Project goal/s	Within five years of project comme walkway from Te Kōwhai village to the Te Otamanui Stream and Waip	Ngāruawāhia township alongside	
Priority works for funding	Suggested works could be impleme private citizens (using contractors of could be undertaken as a whole or Works would need to be undertak	or their own labour). This project in multiple smaller components.	
	Waikato District Council Trails Stra collaboration with the Te Otamanu District Council.		
	 Works required for the Waipā Rive and Te Otamanui Stream outlet ind project management – this incl obtaining landowner agreemen contractors (25% of overall proj construction of a 5.3km gravel a fencing 5.3km with post and ba (\$132,500) native planting alongside the tr (approximately 3000 plants (\$2) development and erection of si surveying (\$20,000). 	clude: udes liaison with landowners and its as well as procurement of ject cost) at \$150 per metre (\$795,000) tten fence at \$25 per metre ack for aesthetic value 6,500)	
	 Works required for completion of t project management – this incl obtaining landowner agreemen contractors (25% of overall proj construction of the remaining t (\$540,000) fencing 3.6km with post and ba (\$90,000) native planting and releasing at (\$18,000) signage (\$3000) surveying (\$10,000) 	udes liaison with landowners and its as well as procurement of ject cost) rack (3.6km) at \$150 per metre tten fence at \$25 per metre	
	Project management/staffing/inci Staff to carry out landowner liaisor Safety requirements, negotiate agr parts of the work as required (e.g.	n, iwi engagement, Health and eements, inspect works, manage	

	reporting and financial management. Incidentals include transport,	
	office overheads, consumables and miscellaneous professional fees.	
	This is estimated to be 25% of the direct project costs.	
Time lag for	If works were implemented at an even pace over a 5-year period, it	L = 3.5
benefits to be	is estimated that the majority of the project benefits would be seen	
realised	approximately 3.5 years after project completion.	
Effectiveness of	The Waipā River (Te Kōwhai to Ngāruawāhia) and Te Otamanui	W = 0.05
works	Lagoon are currently in poor condition with few of the Vision &	
	Strategy desired state aspects being met. These waterways are not	
	swimmable or 100% excluded from stock access, and access for	
	recreation along this stretch of the Waipā River is limited. However,	
	these sites still retain values with the river being of high cultural	
	significance for iwi and the lagoon already being utilised by the Te	
	Kōwhai community for walking.	
	,	
	Some deterioration in these features are expected over the next 20	
	years in the absence of this project, with impacts of the upper	
	catchment and bank stability in the Waipā main stem likely to lead	
	to further decline in water quality and habitat for fish. Decline in	
	values may still be expected even with the project proceeding as it	
	will not address risks related to land use or habitat loss. However,	
	this would be partially offset by an expected substantial	
	improvement in recreation and education opportunities along the	
	river and lagoon. The project outputs would be an asset for the	
	communities providing a walking and biking track between	
	Ngāruawāhia and Te Kōwhai.	
	There would be benefits to this project being conducted in	
	alignment with efforts to fence, stabilise and plant the Waipā River	
	main channel (Project WP 1).	
Risk of technical	Similar walkways have been constructed along the Waikato and	F = 0.92
failure	Waipā Rivers very successfully. Very low risk of project failure due	
	to technical feasibility subject to the path being well set back from	
	erosion prone parts of the riverbank.	
Adoptability	It is estimated that two thirds of landowners would adopt the works	A = 0.675
	if they were fully incentivised. The key challenge is likely to be	
	around getting agreement for a public track along private land,	
	however, Te Otamanui Community Group has made good progress	
	with this to date.	
Information	Very good – information provided by Te Otamanui Community	
quality	Group and Waikato District Council	
Knowledge gaps	The exact route of the track along the Waipā River is yet to be	
and response	determined.	
Socio-political	Low risk that the project will fail to meet its goals over the long term	P = 0.85
risks	due to socio-political risks.	
Project duration	5 years	
(years)		

Up-front cost –			C = 2.04
total for	Task	Cost (\$)	
implementation phase/project	Waipā River walkway		
duration	- Track construction (5.3km)	795,000	
	- Fencing (5.3km)	132,500	
	- Native planting (2250 plants)	26,500	
	- Signage	\$6000	
	- Surveying	20,000	
	Te Otamanui walkway		
	- Track construction (3.6km)	540,000	
	- Fencing (3.6km)	90,000	
	- Native planting (3000 plants)	18,000	
	- Signage	3000	
	- Surveying	10,000	
	Project management/staffing/incidentals (25%)	410,250	
	Total	\$2,051,250	





Te Otamanui Lagoon near Bedford Road (facing upstream). Proposed walkway is on the left side of the photo.

WP 3	Enhancement of Waipā wetlands in priority nutrient	
Priority: Medium	catchments (Waikato district)	BCR value
Relevant unit goal(s)	evant unit goal(s) The quality and flow of water is maintained and enhanced.	
	The catchment has an interconnected network of healthy, indigenous ecosystem types (forest, shrubland, wetlands, lakes, river and stream habitats and margins) supporting native flora and fauna.	
	Wetlands are created or protected and actively managed to enhance multiple functions.	
Name of feature	Waikato district gully wetlands greater than 10 hectares within Waipā catchment	
Brief description of feature	This feature consists of 11 lowland gully ecosystems larger than 10 hectares in size that collectively cover an area of 286 hectares. They are located on the true right bank of the Waipā River within the Waikato district and contain native wetland remnants and native forest remnants (e.g. kahikatea).	
	Catchment modelling undertaken by Waikato Regional Council has identified priority nutrient subcatchments in the Waipā River catchment (lower Mangapiko, Mangawhereo, North west Hamilton). These 11 large gully systems have been identified within the priority nutrient subcatchments as important for water quality.	
	In addition, many of these gully systems are home to rare and/or threatened species such as mudfish, bats, tuna and spotless crake so are also important for biodiversity. In most cases pest willow trees occupy more than 50% of sites but there is a healthy understorey of native plant species. Some sites also have pockets of remnant kahikatea forest.	
	Lakes and wetlands in the Waipā are of high cultural significance providing sustenance, areas of recreation and resources to iwi, hapu and marae. Pā and Papakāinga are common to areas where food is accessible in particular the lakes, wetlands and freshwater springs.	
Desired state to achieve the Vision & Strategy	 Gully wetland ecosystems are protected from stock grazing. They have healthy native plant communities and healthy populations of native fish. They are also valued by the wider community for their aesthetic and cultural values. Iwi and communities have a strong connection to the gully wetlands and are active in their use, protection and restoration. 	

Value of the feature	the Waipā catchment	n the Waikato district gully wetlands in would have a high impact on giving Strategy at a Waipā catchment level.	VS = 25
Key threats to the feature that this			
project addresses	Key threat	Impact on the feature	
	Stock access	Destruction of native plant communities, introduction of weed species.	
	Willow trees	Shade out native species and spread to other sites.	
	Weed species	Compete with native plant communities and are a threat to agriculture.	
Project goal/s	 Within 15 years of project commencement all identified gully wetland systems are 100% fenced to exclude stock. Gully systems are well vegetated with native species where practicable (species that would have been naturally occurring within the gully ecosystem). Known mudfish habitat sites within these gullies are protected from disturbance, and where bats are known to be present site management provides for their habitat 		
Priority works for funding	requirements.Suggested works could be implemented either by an organisation or private citizens (using contractors or their own labour). This project could be undertaken as a whole, or in multiple smaller components.		
	exclude stock with a 5	be fenced at the top of the gully to 5 wire (2 electric) wetland. Ideally this mediately by native planting and rol.	
Willow removal This would be undertaken in circumstances where the wi trees were not providing habitat for a rare or threatened native species and where there was a dense native understorey beneath the willow canopy. Any willow rem should be undertaken in stages using ground based meth (such as treatment with x-tree basal).			
	create a native plant of term. Planting at 1.5m hardy species that wo gully ecosystem (e.g. Native planting costs	d be carried out within open areas to dominated ecosystem over the long- m spacing has been recommended using buld have naturally existed within the cabbage tree, kahikatea, flax, kānuka). have been estimated at \$39,552 per ite preparation, plant purchase, planting	

labour and five releasing events.	
Weed control Most of the gully ecosystems identified have a range of weed species present so a comprehensive weed control plan (along with the native planting) will be essential to ensure success of the project.	
Management plan development For sites where there is no current management plan a management plan should be developed.	
Cost estimates for each site can be found below:	
Mapped area 1: Te Otamanui gully wetland (34ha) - 1km fencing (\$8000) - 8ha of planting along gully banks (\$316,416) - Animal pest control during plant establishment is \$200/ha for 3 years (\$20,400)	
Mapped area 2: Collie Road Wetland (13ha) - Assume 25% of the perimeter (1000m) requires fencing at \$8 per metre (\$8000) - Assume 10m wide buffer planting (1ha) next to new fence (\$39,552)	
 Additional weed control over 30% of the site for 3 years (\$58,500) Animal pest control during plant establishment is \$200/ha for 3 years (\$7800) Management plan (\$10,000) 	
Mapped area 3: Gully wetland west of Te Otamanui Stream gully - Assume 50% of the perimeter (2750 m) requires fencing (\$22,000) - 1.3ha of native planting within open areas (\$48,817) - Animal pest control during plant establishment is \$200/ha for 3 years (\$6000)	
Mapped areas 4 and 5: Crawford Road Wetland and Saulbrey Wetland (total area 100ha) - Assume 50% of the perimeter (16,500 m) requires fencing (\$132,000) - Assume willow control over 50% of the site (\$200,000) - Assume planting over 28% of the site (\$1,107,456) - Assume additional weed control for 3 years over 10% of the site (\$150,000) - Animal pest control during plant establishment is \$200/ha for 3 years (\$60,000)	
Mapped Areas 6, 7 and 8: Ohote Stream gully system	

- Assume 20% (7.4ha) of gully requires willow control (\$29,600)	
- Assume 50% of the perimeter (5500 m) requires fencing	
(\$44,000)	
- Planting perimeter with a 10m wide (5.5ha) buffer of native	
plants (\$217,536)	
- Assume additional weed control for 3 years over 30% (3.7ha)	
of the site (55,500) - Animal pest control during plant establishment is \$200/ha for	
3 years (\$22,200)	
- Management plan (\$10,000)	
Mapped area 9: Collie Road Wetland (10ha)	
- 1.7km fencing (\$13,600)	
 10m planted margin is 1.7ha planting (\$63,838) 2ha weed control over 3 years (\$30,000) 	
- Animal pest control during plant establishment is \$200/ha for	
3 years (\$6000)	
Mapped Area 10: Gully wetland south of Whatawhata	
(approximately 38 ha, 15km perimeter)	
- Assume 50% requires fencing, 7.5km (\$60,000)	
- Assume 20% requires ground based willow control (\$30,400)	
- Assume planting a buffer of native plants in a 5m strip	
around the perimeter (\$296,640)	
- Additional weed control over 30% of the area over 3 years (\$171,000)	
- Animal pest control (for plant establishment) over 3 years	
(\$60,000)	
- Management plan (\$10,000)	
Mapped Area 11: Houghton Road Swamp (21ha, 11km	
perimeter)	
- Assume 10% (1100m) requires fencing (\$8800)	
- Assume 20% requires ground based willow control (\$16,800)	
- Assume planting a buffer of native plants in a 10m strip	
around the perimeter (\$435,072) - Additional weed control over 25% of the area over 3 years	
(\$75,000)	
- Animal pest control (for plant establishment) over 3 years	
(\$12,600)	
- Management plan (\$10,000)	
Project management/staffing/incidentals	
Staff to carry out landowner liaison, iwi engagement, Health	
and Safety requirements, negotiate agreements, inspect	
works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management.	
Incidentals include transport, office overheads, consumables	
and miscellaneous professional fees.	

	This is estimated to be 30% of the direct project costs.	
Time lag for benefits to be realised	If works were implemented at an even pace over a 15-year period, it is estimated that the majority of the project benefits would be seen approximately 2.5 years after project completion.	L = 17.5
Effectiveness of works	These wetlands are currently in a moderate condition when compared to desired state. It is not expected that this will change over the next 20 years if this project is not undertaken. However, if this project is successfully completed then it is expected that wetland condition in 20 years will be closer to the desired Vision & Strategy state than it is currently. These gully wetlands have been identified as a priority due to their importance in attenuating nutrients in these intensively farmed catchments, however they will benefit from stock exclusion and the proposed planting programmes. This project does not address wide-scale and long term pest plant control.	W = 0.15
Risk of technical failure	Risks are mostly related to weed control. There is a moderate risk of project failure due to technical feasibility if weed control isn't well planned and implemented until such time that native plants are well established.	F = 0.82
Adoptability	It is estimated that almost half of landowners would adopt the works if they were fully incentivised. Some may be concerned by loss of marginal grazing areas, however generally the benefits of avoiding loss of stock in wetlands are becoming well recognised.	A = 0.45
Information quality	Poor – management requirements and cost estimates are based largely on aerial photography.	
Knowledge gaps and response	Costings for most sites are largely based off aerial photography combined with some local knowledge. Further work is required during project planning to determine specific amounts of fencing, planting and weed control required.	
Socio-political risks	Low risk that the project will fail to meet its goals over the long term due to socio-political risks.	P = 0.85
Project duration (years)	15 years	

Up-front cost – total	ost – total		C = 5.0
for implementation	Task	Cost (\$)	
phase/project duration	Works at mapped areas 4 & 5	1,649,456	
	Works at mapped area 1	344,816	
	Works at mapped area 2	123,852	
	Works at mapped area 3	76,817	
	Works at mapped areas 6,7 & 8	378,836	
	Works at mapped area 9	113,438	
	Mapped Area 10	590,840	
	Mapped Area 11	558,272	
	Project management/staffing/incidentals (30% of total project cost)	1,150,898	
	Total	4,987,225	







Typical images of all 11 gully wetlands.



Gully wetland 11: Houghton Road Swamp (21ha, 11km perimeter).



Part of gully wetland 4 and 5: Crawford Road Wetland and Saulbrey Wetland.



Gully wetland 9: Collie Road Wetland (10ha).

WP 4	Kaniwhaniwha catchment erosion protection and	
Priority: High	remediation	BCR value
Relevant unit goal(s)	The appropriate management of steep and erosion prone land is promoted and incentivised. Water quality is such that waters within the catchment are swimmable and safe to take food from in all places. Land uses are being adapted to match the capability of the land.	
Name of feature	Kaniwhaniwha subcatchment	
Brief description of feature	The Kaniwhaniwha is an 11,434ha catchment extending from the bush clad slopes of Mt Pirongia to the Waipā River.	
	Approximately 2665ha of land is LUC 6e or 7 in pasture and the catchment has been identified as a priority sediment catchment in the Waipā Catchment Plan. The land use within the catchment is predominantly pastoral farming. 41% of the catchment is in indigenous vegetation.	
	This area was home to many historic pā sites including Purakau and Koromatua. A renowned area for the collection of birds and fisheries for the Ngāti Mahanga, Ngāti Hikairo and Ngāti Apakura hapū.	
	According to water quality monitoring data from Waikato Regional Council, E. coli concentrations of the Kaniwhaniwha Stream at Wright Road are unsatisfactory for swimming 100% of the time.	
Desired state to achieve the Vision & Strategy	 A subcatchment where land use matches capability The stream network has a well vegetated riparian margin (dominated by native species) along its entire length (at least 5m wide) to assist in providing shade, shelter, food and habitat for native fish species. Stock is excluded from all waterways within the catchment. Native fish are abundant and there is a wide diversity of species present including piharau, kōkopu and kāeo (freshwater mussels). There are no manmade barriers to native migratory fish. The stream is swimmable, fishable and has access for recreation. Native bush remnants are densely vegetated, connected to riparian corridors wherever practicable and protected from stock grazing. Native plant regeneration is occurring naturally within native bush remnants. Iwi and communities have a strong connection to the streams and are active in their use, protection and restoration. 	

Impact on Vision & Strategy		ondition the Kaniwhaniwha subcatchment would th impact on giving effect to the Vision & Strategy chment level.	VS = 200
Key threats to the feature that this	Key threat	Impact on feature	
project addresses	Hill country erosion	Estimated to yield more than 8000 tonnes of sediment per year to subcatchment streams and the Waipā River.	
Project goal/s		reduction in suspended sediment in the Stream within 15 years of project nt.	
Priority works for funding	or private citize project could b components. Hill country so	ks could be implemented either by an organisation ens (using contractors or their own labour). This be undertaken as a whole, or in multiple smaller il conservation e managed with open space pole planting at \$3000 (\$975,000).	
	 - 325ha LUC 6 mānuka) at \$ - 65.5km of fe (8-wire and b - 63ha LUC 7 r at \$3000 per - 8km of fenci and batten) - 85.5ha reduce 	e managed with plantation species (pine or 53000 per hectare (\$975,000). ncing the managed LUC 6e land at \$20 per metre batten) (\$1,310,000). nanaged with plantation species (pine or mānuka) hectare (\$189,000). ng managed LUC 7 land at \$20 per metre (8-wire (\$160,000). cing sediment to waterways outside LUC class 6e, 7	
	seepages, et - 28km fencing	t \$5000 per hectare (e.g. dewatering, retiring c) (\$427,500). g existing indigenous forest cover at \$25 per metre patten) (\$700,000).	
	Staff to carry of Safety required manage parts of project reporti	ement/staffing/incidentals out landowner liaison, iwi engagement, Health and ments, negotiate agreements, inspect works, of the work as required (e.g. fencing or planting), ng and financial management. Incidentals include ce overheads, consumables and miscellaneous nes.	
	This is estimate	ed to be 25% of the direct project costs.	
Time lag for benefits to be realised	If works were i period, it is est	mplemented at an even pace over a 15-year imated that the majority of the project benefits approximately 13-14 years after project	L = 13.5
Effectiveness of works	The Kaniwhani upper catchme objectives of tl are in moderat	wha subcatchment varies in condition with the ent being fully vegetated and largely meeting the ne Vision & Strategy. Other parts of the catchment ce condition with some of the Vision & Strategy spects being met, although the stream is not	W = 0.2

Risk of technical	 considered swimmable due to high levels of E. coli. that over the next 20 years there could be a slow de condition of the catchment in the absence of this princluded here address several threats to the feature anticipated that if the project is fully completed the will be close to the Vision & Strategy state being ach aspects related to land use matching capability and sediment to waterways. There would also be second to biodiversity. There would be advantages in this pricarried out in alignment with Project WP 5 which ach different values within the same subcatchment. Risks are mostly related to establishment of planting 	eterioration in oject. Works and it is catchment nieved for reduction of dary benefits project being ldresses gs or loss of	F = 0.92
failure	works due to severe erosion before they are establish However, proposed priority actions are widely used for managing hill country erosion. There is a low ris failure due to technical feasibility.	and accepted	
Adoptability	It is estimated that about a quarter of landowners we the works if they were fully incentivised. Uptake of of LUC class 6e and 7 land may be low, however the momentum that has been created in the catchment years that may provide encouragement for others. approach to managing erosion on farm is also encou- this should be addressed in the development of the plan(s).	management re is some in recent Flexibility in uraged and	A = 0.225
Information quality	Average – estimates are based on modelled information input from catchment officers who are familiar with subcatchment and are working with landowners to undertake similar works.	the help them	
Knowledge gaps and response	Estimates of LUC classes 6e, 7 and 8 come from a de exercise. Farm scale information will need to be gat of this project.	•	
Socio-political risks Project duration	Low risk that the project will fail to meet its goals ov term due to socio-political risks. 15 years	ver the long	P = 0.85
(years)			
Up-front cost –			C = 5.9
total for implementation	Task	Cost (\$)	
phase/project duration	Pole planting erosion prone LUC class 6e land (325ha)	975,000	
	Plantation species on erosion prone LUC class 6e land (325ha)	975,000	
	Fencing managed LUC class 6e land (65.5ha)	1,310,000	
	Plantation species on LUC class 7 land (63ha)	189,000	
	Fencing managed LUC class 7 land (8km)	160,000	
	Treating erosion outside LUC class 6e, 7 and 8 land (85.5ha)	427,500	
	Fencing existing indigenous vegetation (28km)	700,000	
	Project management/staffing/incidentals (25%)	1,184,125	

Total	\$5,920,625
-------	-------------





Topography of the Kaniwhaniwha catchment, including high erosion class land.



Open-space pole planting on high erosion class land in the Kaniwhaniwha catchment.



A retired wetland sidling in the Kaniwhaniwha catchment, reducing sedimentation outside LUC class 6e, 7 and 8 land.

WP 5	We shall be shall be easily as a state of the first test	
Priority: Very high	Kaniwhaniwha catchment streams fish habitat rehabilitation and restoration of forest remnants	BCR value
Relevant unit goal(s)	The catchment has an interconnected network of healthy, indigenous ecosystem types (forest, shrubland, wetlands, lakes, river and stream habitats and margins) supporting native flora and fauna. Indigenous fish have access throughout the river catchments (except where natural barriers exist) and the catchment has an abundance of taonga species such as kōkopu, piharau, tuna, kōura and kāeo.	
Name of feature	Kaniwhaniwha subcatchment	
Brief description of feature	 A 50km long stream network within the Kaniwhaniwha catchment has been identified by fish experts as being important habitat for native fish and a priority for fish habitat rehabilitation (where fish habitat is lacking). Waterways include: Kaniwhaniwha Stream – a 20km long stream flowing from the forested slopes of Mt Pirongia (near the village of Te Pahu) to join the Waipā River near Whatawhata. Rangitukia Stream – a 13km long stream flowing from Mt Pirongia in the vicinity of Corcoran Road, Te Pahu. Te Pahu Stream – a 10.6km long stream flowing from Mt Pirongia in the vicinity of Rolley Road, Te Pahu, to join the Rangitukia Stream near the end of Simmond Road, Te Pahu. Te Kauri Stream – a 3.5km long stream flowing from Mt Pirongia in the vicinity of Limeworks Loop Road, Te Pahu, to join the Kaniwhaniwha Stream near Fillery Road. Tawhitiwhiti Stream – a short stream with a steep gradient flowing from the bush line on Mt Pirongia for approximately 3.7km downstream to the Te Pahu Stream. 	
	There are also numerous forest remnants within the Kaniwhaniwha catchment. Five of these have been identified as being within the top 30% of biodiversity priorities within the Waikato and Waipā River catchments. These sites range in size from 0.7ha to 32ha.	
	This area was home to many historic pā sites including Purakau and Koromatua. A renowned area for the collection of birds and fisheries for the Ngāti Mahanga, Ngāti Hikairo and Ngāti Apakura hapū.	
	According to water quality monitoring results on the Waikato Regional Council website, the Kaniwhaniwha Stream is unsatisfactory for swimming 100% of the time due to high levels of E.coli.	

Desired state to achieve the Vision & Strategy	 The stream network has a (dominated by native spe 5m wide) to assist in provider for native fish species. Stock is excluded from all Native fish are abundant present including piharau mussels). There are no manmade b The stream is swimmable recreation. Native bush remnants are riparian corridors wherev stock grazing. Native plan 		
	within native bush remna - Iwi and communities have	nts. e a strong connection to the streams	
Impact on Vision		e, protection and restoration. Kaniwhaniwha catchment Streams	VS = 200
& Strategy	and adjoining forest fragme	ents would have a very high impact on Strategy at a Waipā catchment level.	v3 - 200
Key threats to the feature that this	Key threat	Impact on the feature	
project addresses	Lack of riparian vegetation, streambank erosion and sedimentation.	Degraded fish habitat	
	Lack of in-stream woody debris	Reduction in cover and habitat for native fish	
	Incorrectly installed waterway crossings are a barrier to native fish	Large areas of fish habit are unused. Fish unable to complete their life cycle.	
	Streambank erosion	Estimated to yield 932 tonnes of sediment per year	
	Fragmentation of forest remnants	Affects the viability of the forest fragment through increasing edge effects, increasing potential for weed and animal pest invasion. Also reduces the habitat available for native species.	
	Stock access to native forest remnants	Stock prevent native regeneration and open up areas to plant pests.	
Project goal/s	minimum 5m fence setba - Riparian margins are vege exotic trees for erosion pr provide stream shade and	ally fenced to exclude stock with a ck. etated on both sides with a mixture of rotection and native tree species that d enhance habitat for adult native fish d areas for recreational access).	

Priority works for	 Woody structures provide in-stream habitat for native fish at approximately 64 locations along the Kaniwhaniwha Stream. There are healthy populations of native fish species including tuna (eel), koura, banded kokopu and piharau. All identified forest remnants are fenced to exclude stock and connected to other forest remnants and riparian areas where possible. Native planting fills in any open areas within forest fragments and provides a buffer around the outside from 'edge effects'. 	
Priority works for funding	 and provides a buffer around the outside riohr edge effects. Suggested works could be implemented either by an organisation or private citizens (using contractors or their own labour). This project could be undertaken as a whole, or in multiple smaller components. Fencing waterways Carry out fencing (at least 5 wire with 2 electric wires unless flooding is a common issue) along the waterways identified. This shall have a minimum 5m setback from the top of the streambank. Fencing costs are estimated at \$8 per metre. Cost estimates assume that 50% of the waterways are unfenced or require fences to be moved back to allow for planting. Cost estimates are as follows: Kaniwhaniwha Stream Fencing (20km fence length) – \$160,000 Rangitukia Stream Fencing (13km fence length) – \$104,000 Te Pahu Stream Fencing (10.6km fence length) – \$28,000 Ta Kauri Stream Fencing (3.7km fence length) – \$29,600 Planting waterways Undertake native and exotic riparian planting within the fenced area and carry out associated weed control and maintenance. Cost assume that 50% of each waterway requires planting at a cost of \$37,552 per hectare (including site prep, plant purchase, planting labour and five releasing events). Kaniwhaniwha Stream Planting (5.5ha) – \$244,088 Te Pahu Stream Planting (5.5ha) – \$244,088 Te Pahu Stream Planting (1.75ha) – \$65,716 Tawhitiwhiti Stream Planting (1.8ha) - \$67,593 In-stream woody debris Construct in-stream woody debris structures on Kaniwhaniwha Stream for native fish habitat (4 structures per 500 m from the corner of Fillery Road and Limeworks Loop Road downstream to Smith Road) over an 8km stretch.	
	undertaken by a suitably experienced practitioner to ensure that it does not exacerbate bank erosion. Consent may be required for this work.	
The estimated cost of woody debris structures (including site investigation, design and installation) is \$236,712 plus \$20,000 for resource consents. This cost estimate is generous and cost savings would be made if one resource consent application		
--	--	
covered all woody debris structures and if multiple structures were installed at a time.		
Remediation of fish barriers Locations of barriers to fish passage are investigated and work		
undertaken to remedy these barriers. On the Rangitukia Stream		
at least three barriers are estimated to require being remedied.		
Remediation of fish barriers is estimated at \$30,000		
Management of forest remnants		
Fencing forest remnants		
Fence any unfenced forest remnants identified (see map) to		
exclude stock with a minimum 5 wire (2 electric) fence.		
- Forest remnant in the vicinity of Smith Road (32ha, 7km		
perimeter) – assume 70% (4.9km) of fencing or fence upgrade		
is required around the perimeter (\$39,200).		
 Forest remnants in the vicinity of Grove Road and Te Pahu Road (totalling 6.4ha) – assume 500m of fencing is required 		
(\$4000).		
- Kahikatea fragments between Whittaker Road and Te Pahu		
Stream (1.7ha block and 0.7ha block) – assume 800m of fencing or fence upgrade is required (\$6400).		
- Patchy forest remnants off Limeworks Loop Road		
(approximately 10ha and 4km perimeter if connected) –		
assume 50% of perimeter fencing is required (\$16,000).		
 Forest fragments close to Martelletti Road on the Rangitukia Stream (8ha) – no fencing required. 		
Planting within and around forest remnants Carry out native planting to fill gaps and protect forest remnants		
from edge effects if required. This is estimated to cost \$37,552		
per hectare including site preparation, plant purchase, planting		
labour and five releasing events.		
- Forest remnant in the vicinity of Smith Road (32 ha, 7km		
perimeter) – assume 10% (3ha) of the area requires planting (\$112,656).		
- Forest remnants in the vicinity of Grove Road and Te Pahu		
Road (totalling 6.4ha) – assume 1ha requires infill planting (\$37,552).		
- Kahikatea fragments between Whittaker Road and Te Pahu		
Stream (1.7ha block and 0.7ha block) – assume 0.5ha of		
planting is required (\$18,776).		
 Patchy forest remnants off Limeworks Loop Road (approximately 10ha and 4km perimeter if connected) – 		
(approximately zona and man permeter in connected)		

assume 20% (2ha) of the area requires native planting	
(\$75,104).	
- Forest fragments close to Martelletti Road on the Rangitukia	
Stream (8ha) – no planting required.	
Weed control in and around forest remnants	
Some sites might be particularly weedy and require additional	
plant pest control to ensure success of native plantings and	
regeneration of native trees. A cost estimate of \$2800 per	
hectare for weed spraying using a knapsack has been estimated	
per year for three years across the areas as follows:	
 Forest remnant in the vicinity of Smith Road (32ha, 7km 	
perimeter) – weed control across 10% (3.2ha) of the site	
including within the 3ha planted area (\$26,880).	
- Forest remnants in the vicinity of Grove Road and Te Pahu	
Road (totalling 6.4ha) – weed control across 20% (1.2ha) of the	
site including within the 1ha planted area (\$10,080).	
- Kahikatea fragments between Whittaker Road and Te Pahu	
Stream (1.7ha block and 0.7ha block) – weed control across	
20% (0.5ha) of the site (\$4200).	
- Patchy forest remnants off Limeworks Loop Road	
(approximately 10ha and 4km perimeter if connected) – weed	
control across 20% (2ha) of the site (\$16,800).	
- Forest fragments close to Martelletti Road on the Rangitukia	
Stream (8ha) – weed control across 10% (0.8ha) of the site (\$6720).	
(\$0720).	
Animal pest control	
Possum control may be required within forest remnants to assist	
with the establishment of native plantings. The cost estimates	
provided below provide are \$600 per hectare for 3 years of	
possum control using bait stations. The cost includes purchase	
and establishment of bait stations at one station per hectare and	
labour and bait to check and refilling of bait stations.	
- Forest remnant in the vicinity of Smith Road (32ha, 7km	
perimeter) – \$19,200.	
- Forest remnants in the vicinity of Grove Road and Te Pahu	
Road (totalling 6.4ha) – \$3840.	
- Kahikatea fragments between Whittaker Road and Te Pahu	
Stream (1.7ha block and 0.7ha block) – \$1800.	
 Patchy forest remnants off Limeworks Loop Road 	
(approximately 10ha and 4km perimeter if connected) – \$6000.	
Project management/staffing/incidentals	
Staff to carry out landowner liaison, iwi engagement, Health and	
Safety requirements, negotiate agreements, inspect works,	
manage parts of the work as required (e.g. fencing or planting),	
project reporting and financial management. Incidentals include	
transport, office overheads, consumables and miscellaneous	
professional fees.	

	This is estimated to be 30% of the direct project costs.	
Time lag for	If works were implemented at an even pace over a 15-year	L = 13.5
benefits to be	period, it is estimated that the majority of the project benefits	L = 13.5
realised	would be seen approximately 13-14 years after project	
Teanseu	commencement.	
Effectiveness of	The Kaniwhaniwha subcatchment varies in condition with the	W = 0.17
works	upper catchment being fully vegetated and largely meeting the	VV - 0.17
WUIKS	objectives of the Vision & Strategy. Other parts of the catchment	
	are in moderate condition with some of the Vision & Strategy	
	desired state aspects being met. It is expected that over the next	
	20 years there could be a slow deterioration in condition of the	
	catchment in the absence of this project. Works included here	
	address several threats to the feature and it is anticipated that if	
	the project is fully completed then the catchment will be close to	
	the Vision & Strategy state being achieved for aspects related to	
	fisheries and biodiversity in 20 years' time. The project does not	
	address land use in the middle to lower catchment, however the	
	proposed fencing and planting works will assist in protecting and	
	restoring water quality at this site. There would be advantages in	
	this project being carried out in alignment with Project WP 4	
	which addresses different threats and values within the same	
	subcatchment.	
Risk of technical	There is a moderate risk of project failure due to technical	F = 0.82
failure	feasibility. Risks are mostly related to establishment of plantings	F – 0.02
Tallure	or loss of works due to flooding. Construction of in-stream fish	
	habitat is a relatively recently applied tool in these environments	
	and there is still some uncertainty around their longevity. Risk of	
	failure can be minimised by works being designed and	
	constructed by an appropriately experienced practitioner.	
Adoptability	It is estimated that almost half of landowners would adopt the	A = 0.45
Αυοριασίπιγ	works if they were fully incentivised. The extent of the fencing	A = 0.45
	setbacks may be a challenge in terms of uptake. If there is	
	already fencing close to the streambank in places (i.e. with a	
	narrow riparian margin) landowners may be unwilling to move	
	fences back to allow room for native planting. Loss of fences to	
	flooding may also be a deterrent for landowners who are	
	concerned about maintenance costs. This can be mitigated by	
	the use of 5m setbacks and a fencing standard appropriate for	
	the location.	
	There are some existing projects along this reach that provide a	
	good example of what can be achieved with larger riparian	
	margins.	
Information	Average – estimates are based on aerial photographs, Waipā	
quality	catchment riparian surveys and input from catchment officers	
-11	who are familiar with the reach and are working with landowners	
	to help them undertake similar works.	
Knowledge gaps	It is unknown specifically how much fencing already exists. This	
and response	would need to be established as part of the project planning.	
	Location of fish barriers, and location and design of in-stream	
	woody debris structures would need to be determined in the	
	early stages of the project.	

Socio-political	Low risk that the project will fail to meet its goals over	P = 0.85	
risks Project duration	term due to socio-political risks. 15 years		
(years)			
Up-front cost –			
total for	Task	Cost (\$)	
implementation phase/project	Kaniwhaniwha Stream fencing (20km)	160,000	
duration	Kaniwhaniwha Stream planting (10ha) including plant establishment	375,520	
	Rangitukia Stream fencing (13km of bank)	104,000	
	Rangitukia Stream planting (6.5ha)	244,088	
	Rangitukia Stream fish barrier remediation	30,000	
	Te Pahu Stream fencing (10.6km of streambank)	84,800	
	Te Pahu Stream planting (5.3ha)	199,025	
	Te Kauri Stream fencing (3.5km of streambank)	28,000	
	Te Kauri Stream planting (1.75ha)	65,716	
	Tawhitiwhiti Stream fencing (3.7km of streambank)	29,600	
	Tawhitiwhiti Stream planting (1.8ha)	67,593	
	In-stream woody debris	236,712	
	Resource consent for weedy debris structures	20,000	
	Remediation of fish barriers (3)	30,000	
	Fencing forest fragments (10.2km)	65,600	
	Planting in and around forest remnants	244,088	
	Weed control in and around forest remnants	64,680	
	Animal pest control	31,800	
	Project management and planning (30%)	624,366	
	Total	2,705,588	





The middle reaches of the Kaniwhaniwha Stream, with a forest remnant in the top right corner of the photo.



An unfenced section of Kaniwhaniwha Stream. The water levels are higher than usual in this photo.



An unfenced section of Rangitukia Stream.



A section of Te Pahu Stream where it is recommended that the riparian fence be moved back and the margin planted in native plants.



Te Pahu Stream in the foreground and native kahikatea forest remnants in the background.

WP 6	Enhancement of Waipā wetlands in priority nutrient	
Priority: Medium	catchments (Waipā district)	BCR value
Relevant unit goal(s)	The quality and flow of water is maintained and enhanced. The catchment has an interconnected network of healthy, indigenous ecosystem types (forest, shrubland, wetlands, lakes, river and stream habitats and margins) supporting native flora and fauna. Wetlands are created or protected and actively managed to enhance multiple functions.	
Name of feature	Waipā district gully wetlands greater than 10ha and located within Waipā catchment priority nutrient areas.	
Brief description of feature	Eight gully ecosystems containing remnant wetlands and forest fragments. The total area covered by these sites is 215ha. These are located on the true right bank of the Waipā River and contain wetlands with remnants of native wetland vegetation, and remnant forest fragments (e.g. kahikatea). Catchment modelling undertaken by Waikato Regional Council has identified priority nutrient subcatchments in the Waipā River catchment (lower Mangapiko, Mangawhereo and northwest of Hamilton). These large gully systems have been identified within the priority nutrient subcatchments as important for water quality. In addition, many of these gully systems are home to rare and/or threatened species such as mudfish, bats, tuna and spotless crake so are also important for biodiversity reasons. In most cases pest willow trees occupy a large proportion of sites but there is a healthy understorey of native plant species. Some sites also have pockets of remnant kahikatea	
Desired state to achieve the Vision & Strategy	 forest. Historically, the gullies and wetlands of the Waipā River catchments provided sustenance for iwi, hapū and marae. Tuna, and birds were the staple foods for tāngata whenua. These were active areas for gathering foods. Gully wetland ecosystems are protected from stock grazing. They have healthy native plant communities and healthy populations of native fish. They are valued by the wider community for their aesthetic and cultural values. Iwi and communities have a strong connection to the gully wetlands and are active in their use, protection and restoration. 	
Impact on Vision & Strategy	In a restored condition the Waipā district gully wetlands would have a very high impact on giving effect to the Vision & Strategy at a Waipā catchment level.	VS = 25

Key threats to the			
feature that this	Key threat	Impact on the feature	
project addresses	Further clearance of native vegetation within gully wetlands	Reduced habitat for native flora and fauna and game birds, loss of nutrient attenuation areas, loss of wetland areas to slow flood flows.	
	Stock access	Destruction of native plant communities, introduction of weed species.	
	Willow trees	Shade out native species and spread to other sites.	
	Weed species	Compete with native plant communities and are a threat to agriculture.	
Project goal/s	stock and protected (e.g. large scale drain - Gully systems are we practicable. - Known mudfish habi protected from distu	etland systems are fenced to exclude from extensive land drainage practices n digging). ell vegetated with native species where tat sites within these gullies are irbance. wn to be present site management	
Priority works for funding	Suggested works could organisation or private	l be implemented either by an citizens (using contractors or their own ould be undertaken as a whole, or in	
	exclude stock. Ideally native planting and ass	be fenced at the top of the gully to this would be followed immediately by sociated weed control. Fencing should m of 5 wire (2 electric) and this has been er metre	
	trees are not providing species and where the the willow canopy. An in stages using ground	ken in circumstances where the willow g habitat for a rare or threatened native re is a dense native understorey beneath y willow removal should be undertaken based methods (such as treatment with mated cost of this is \$4000 per hectare.	
	create a native plant d term. Planting at 1.5m hardy species that wou	be carried out within open areas to ominated ecosystem over the long a spacing has been recommended using ald have naturally existed within the gully ge tree, kahikatea, flax, kānuka). Native	

planting has been estimated to cost \$39,552 per hectare including site preparation, plant purchase, planting labour and five releasing events.	
Weed control	
Most of the gully ecosystems identified have a range of weed species present so a comprehensive weed control plan (along with the native planting) will be essential to ensure success of the project. Weed control costs are generally estimated at \$5000 per hectare. This is based on using a knapsack sprayer	
and assumes that the site is very weedy.	
Animal pest control	
Possum control may be required in areas where native planting is to be undertaken. The estimated cost for this work is \$600 per hectare for three years using bait stations.	
Management plan development	
For sites where there is no current management plan a management plan should be developed.	
Assumptions and cost estimates for each site can be found below.	
Mapped area 12 – Tuhikaramea Stream tributary gully (38.7 ha, 14km perimeter).	
 Assume 5% (800 m) requires fencing (\$5600). Assume 35% (13.5ha) requires ground based willow control (\$54,180). 	
 Assume 25% of the area requires native planting, 13.5ha (\$533,952). 	
 Additional weed control over 30% (11.6ha) of the area over 3 years at a cost of \$5000 per hectare using a knapsack (\$174,150). 	
- Animal pest control (for plant establishment) over 3 years (\$23,220).	
- Management plan (\$10,000).	
Mapped area 13 – Mangahia Stream gully (36ha, 13km perimeter).	
 Assume 10% requires fencing, 1.3km (\$10,400). Assume 40% (14.4ha) requires ground based willow control (\$57,600). 	
- Assume planting a buffer of native plants 5m wide around the perimeter, 6ha (\$237,312).	
- Additional weed control over 40% (14.4ha) of the area over 3 years (\$216,000).	
- Animal pest control (for plant establishment) over 3 years (\$21,600).	
- Management plan (\$10,000).	

ГТ	Г	
	Mapped area 14 – Mangaotama gully and wetland (total area 80ha).	
	- Assume the area downstream of State Highway 39 (35ha and	
	10km perimeter) is 10% unfenced, requires some infill	
	planting (approx 5ha) and weed control (e.g. willow) 20% of	
	the area.	
	- Assume the area upstream of Hams Road (4.2ha and 1.5km	
	perimeter) is 90% unfenced, requires 1.5ha native planting	
	(10 m wide riparian margin) and additional weed control over	
	20% of the area).	
	- The middle section between Hams Road and the state	
	highway is already being intensively managed and only	
	requires animal pest control for plant establishment.	
	Total fencing cost (2350 m) is \$18,800	
	Total planting cost (6.5ha) is \$245,222	
	Total weed control over 3 years (in addition to native plant	
	establishment) (20% of area is 7.8ha) is \$117,000	
	Animal pest control for native plant establishment (80ha at	
	\$200/ha) is \$48,000	
	Management plan is \$10,000.	
	Mapped area 15 - Patterson Road Wetland (17 ha, 6.7km	
	perimeter)	
	- Assume 30% (2km) requires fencing (\$16,081).	
	- Assume 20% (3.4ha) requires ground based willow control	
	(\$13,600).	
	 Assume planting a buffer of native plants 5m wide around the perimeter, 3.4ha (\$134,476). 	
	- Additional weed control over 20% (3.4ha) of the area for 3	
	years (\$51,000).	
	- Animal pest control (for plant establishment) over 3 years	
	(\$10,200).	
	- Management plan (\$10,000).	
	Mapped area 16 – gully wetland, forest fragment and	
	waterway in between (near Frontier Road, Pirongia)	
	- Assume 50% (5.3km) requires fencing (\$42,400).	
	 Assume planting a buffer of native plants 10m wide around 	
	50% (5.3ha) of the perimeter (\$209,625).	
	- Additional weed control over 10% (2.7ha) of the area for 3	
	years (\$40,500).	
	- Animal pest control (for plant establishment) over 3 years	
	(\$16,560). Management plan (\$10,000)	
	- Management plan (\$10,000).	
	Mapped area 17 – Mangawhero Stream lower catchment	
	margins (15ha, 6km perimeter)	
	- Assume 50% (3km) requires fencing (\$24,000).	
	- Assume 30% (4.5ha) requires ground based willow control	
	(\$18,000).	

	 Assume planting a buffer of native plants 10m wide around the perimeter, 6ha (\$237,312). Additional weed control over 20% (3ha) of the area for 3 years (\$45,000). Animal pest control (for plant establishment) over 3 years (\$9000). Management plan (\$10,000). Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals	
	include transport, office overheads, consumables and miscellaneous professional fees. This is estimated to be 30% of the direct project costs.	
Time lag for benefits to be realised	If works were implemented at an even pace over a 10-year period, it is estimated that the majority of the project benefits would be seen approximately 5 years after project completion.	L = 15
Effectiveness of works Risk of technical failure Adoptability	These wetlands are currently in a moderate condition when compared to desired state. It is not expected that this will change over the next 20 years if this project is not undertaken. However, if this project is successfully completed, then it is expected that wetland condition in 20 years will be closer to the desired Vision & Strategy state than it is currently. These gully wetlands have been identified as a priority due to their importance in attenuating nutrients in these intensively farmed catchments, however they will benefit from stock exclusion and the proposed planting programmes. This project does not address wide-scale and long term pest plant control. Risks are mostly related to weed control. There is a high risk of project failure due to technical feasibility if weed control isn't well planned and a focus given to key high priority weeds that can be managed to very low levels until native plants dominate. It is estimated that almost half of landowners would adopt the	W = 0.15 F = 0.82 A = 0.45
	works if they were fully incentivised. Some may be concerned by loss of marginal grazing areas however generally the benefits of avoiding loss of stock in wetlands are becoming well recognised.	
Information quality	Poor – management requirements are based on expert knowledge but quantity of work required is based largely on aerial photography.	
Knowledge gaps and response	Costings for most sites are largely based off aerial photography combined with some local knowledge. Further work is required during project planning to determine specific amounts of fencing, planting and weed control required.	
Socio-political risks	Low risk that the project will fail to meet its goals over the long term due to socio-political risks.	P = 0.85

Project duration (years)	10 years		
Up-front cost –			C = 3.50
total for	Task	Cost (\$)	
implementation phase/project	Mapped area 12	801,102	
duration	Mapped area 13	552,912	
	Mapped area 14	439,022	
	Mapped area 15	235,356	
	Mapped area 16	319,085	
	Mapped area 17	343,312	
	Project management/staffing/incidentals (30%)	807,236	
	Total	3,498,025	







Gully wetland 14 (downstream section): Mangaotama gully and wetland (total area 80ha).



Gully wetland 15: Patterson Road Wetland (17 ha, 6.7km perimeter).

WP 7	Restoration of priority lowland kahikatea remnants (and associated wetlands) between Te Kūiti and	
Priority:	Templeview	
Medium	Templeview	BCR value
Relevant unit	The catchment has an interconnected network of healthy,	
goal(s)	indigenous ecosystem types (forest, shrubland, wetlands,	
	lakes, river and stream habitats and margins) supporting	
	native flora and fauna.	
Name of feature	Waipā River catchment kahikatea remnants and associated	
	wetlands	
Brief description	Within the Waipā catchment only 2.07% of the conifer-	
of feature	dominated forests (kahikatea) remain (approximately 170ha).	
	Most have been cleared for pastoral farming and most of	
	what remains has been degraded by grazing, land drainage	
	weed infestation and animal pests. Most remaining kahikatea	
	forest remnants are small (less than 10ha) and fragmented	
	and require further management to ensure their existence	
	long term.	
	The remnants selected for this project include 10 small	
	kahikatea remnants (and associated wetlands) totalling an	
	area of 62.5ha, located within the Waipā River catchment	
	between Te Kūiti and Whatawhata. These remnants have	
	been identified as being within the top 30% of biodiversity	
	sites in the Waikato catchment and/or important habitat for	
	the 'at risk' black mudfish. Five of the remnants are located	
	near McGregor Road near Hamilton, four are located near Te	
	Kūiti (one of which has an associated wetland where there is a	
	healthy population of mudfish) and one other is located near	
	Kakepuku Mountain south of Te Awamutu.	
	Kahikatea provide an important food resource in the koroi	
	berry which was skilfully harvested by Māori and also enticed	
	birdlife to the tree, for capture.	
Desired state to	- Kahikatea remnants and their associated wetlands are	
achieve the Vision	densely vegetated with native vegetation, connected to	
& Strategy	riparian corridors wherever practicable and protected from	
	stock grazing.	
	- Native plant regeneration occurs naturally within the native	
	forest remnants and associated wetlands.	
	- Where wetlands retain healthy populations of black mudfish	
	these are protected.	
	- Iwi and communities have a strong connection to these	
Impact on Vision	areas and are active in their use, protection and restoration. In a restored condition the Waipā River catchment kahikatea	VS = 1.5
& Strategy	remnants and associated wetlands would have a high impact	v3 – 1.3
a sualegy		
	on giving effect to the Vision & Strategy at a local level.	

Key threats to the		1 1	
feature that this	Key threat	Impact on the feature	
project addresses	Further fragmentation of forest fragments	Affects the viability of the forest fragment through increasing edge effects, increasing potential for weed and animal pest invasion. Also reduces the habitat available for native species.	
	Stock access to native forest fragments	Stock prevent native regeneration and open up areas to plant pests.	
Project goal/s	 All forest remnan are 100% fenced Edge effects have 	this project commencing: ts identified and their associated wetlands to exclude stock. been reduced through native planting os and around the perimeter of kahikatea	
Priority works for funding	Suggested works co organisation or priv	uld be implemented either by an ate citizens (using contractors or their own at could be undertaken as a whole, or in mponents.	
	fencing, planting an on aerial photograp	n is required to determine the amount of d weed control required. However, based hs and local knowledge the following nptions have been made:	
		erally be a minimum of 5 wire (2 electric) ated at a cost of \$8 per metre.	
	•	es – 50% of the perimeter still remains to lates to 2.8km of fencing (\$22,400).	
		s/wetlands near Te Kūiti – fencing is e 7.1km perimeter of these areas	
	around the perimet 1.5ha of planting. T hectare (\$56,328) in	es – some infill planting will be required er of these sites. This is estimated to total The cost of this is estimated at \$37,552 per including site preparation, native plant abour and five releasing events.	
	be required over 10	es – general weed control is estimated to 1% of the sites (2.2ha) using a backpack nately \$2800 per hectare (\$6160) for three	

	Kahikatea remnant near Kakepuku – weed control is estimated to be required over 10% (1ha) of the site to	
	promote regeneration of native species. Using a backpack	
	sprayer this is estimated to cost \$8400 over three years.	
	Kahikatea remnants/wetlands near Te Kūiti – some weed	
	control is likely to be required within the site once it is fenced	
	to promote the regeneration of native species around the	
	perimeter. Using a vehicle with spray unit to treat a 5m wide	
	area around the perimeter (3.5ha) is estimated to cost \$1400 per hectare (\$4900) per year for three years (\$14,700).	
	Animal pest control	
	McGregor Road sites – possum control may be required at	
	these sites to assist with native plant establishment. The cost	
	of this using bait stations is estimated at \$200 per hectare per	
	year for three years (2.2ha x \$200 per ha x 3 years is \$1320).	
	Project management/staffing/incidentals	
	Staff to carry out landowner liaison, iwi engagement, Health	
	and Safety requirements, negotiate agreements, inspect	
	works, manage parts of the work as required (e.g. fencing or	
	planting), project reporting and financial management.	
	Incidentals include transport, office overheads, consumables and miscellaneous professional fees.	
	This is estimated to be 20% of the direct project costs.	
Time lag for	If works were implemented at an even pace over a 5-year	L = 5.5
benefits to be	period, it is estimated that the majority of the project benefits	
realised	would be seen within 1 year of project completion.	
Effectiveness of	These fragments are currently in a poor condition when	W = 0.1
works	compared to desired state. They also remain at risk of further	
	fragmentation and loss of important hydrological conditions	
	to sustain them, and as a result it is expected that they will	
	deteriorate slowly over the next 20 years if this project is not	
	undertaken. If this project is successfully completed, then it is expected that these kahikatea fragments will be in an	
	improved condition in 20 years' time due to increased	
	regeneration of native species and reduction in weeds.	
	However, this project does not address the concerns around	
	retention of wetland hydrology at these sites.	
Risk of technical	Risks are mostly related to failure to control weeds. There is a	F = 0.92
failure	low risk of project failure due to technical feasibility.	
Adoptability	It is estimated that about two thirds of landowners would	A = 0.63
	adopt the works if they were fully incentivised. Some	
	landowners may be concerned about the perceived loss of	
	shelter areas for stock, or the practicalities of smaller fenced areas on farm. However generally there is good support for	
	this type of work and for the retention of these rare features.	
	Instype of work and for the retention of these rare redutes.	

Information	Average information – based on judgement of an	expert with	
quality	some local knowledge. Fencing and planting requirements are		
	based on aerial photographs.		
Knowledge gaps	Specific quantities of fencing, planting and pest co	ontrol	
and response	required would need to be established as part of t	he project	
	planning.		
Socio-political	Very low risk that the project will fail to meet its goals over		P = 0.97
risks	the long term due to socio-political risks.		
Project duration	5 years		
(years)			
Up-front cost –			C = 0.21
total for implementation phase/project duration	Task	Cost (\$)	
	Fencing (9.9km)	79,200	
	Possum control (2.2ha)	1320	
	Weed control for 3 years	41,580	
	Native planting (1.5ha)	56,328	
	Project management/staffing/incidentals (20%)	35,686	
	Total	214,114	



DSCLAIMER: While Waikato Regional Council has exercised all reasonable skill and care in controlling the contents of this information, Waikato Regional Council accepts no liability in contract, tort or otherwise howsoever, for any loss, damage, injury or expense (whether direct, indirect or consequential) ansing out of this information or its use by you.



DISCLAIMER: While Waikato Regional Council has exercised all reasonable skill and care in controlling the contents of this information, Waikato Regional Council accepts no liability in contract, tort or otherwise howsoever, for any loss, damage, injury or expense (whether direct, indirect or consequential) ansing out of the provision of this information or its use by you.



WP 8			
Priority: High	Enhanceme	ent of water levels in the Moanatuatua Wetland	
Relevant unit goal(s)	indigenous e	ent has an interconnected network of healthy, cosystem types (forest, shrubland, wetlands, lakes, eam habitats and margins) supporting native flora	BCR value
	enhance mu Where possi	e created or protected and actively managed to Itiple functions. ble, the natural functioning of floodplains and other	
	ephemeral v	vetland sites is restored and maintained.	
Name of feature	Moanatuatu	a Wetland	
Brief description of feature	remaining of ecological di found there.	uatua is an approximately 140ha peat bog – the only its type that once covered 50,000ha in the Hamilton strict. The rare peat-forming <i>Sporodanthus</i> is still Ownership is split between Department of n (114ha) and Waikato-Tainui (23ha).	
	Both remnar their small si extremely su		
	(medicines) The soils we	the wetland provided sustenance and rongoā to tāngata whenua with its unique species of plants. re also used for cultural activities including the yes and strengthening of taonga (treasures).	
Desired state to achieve the Vision & Strategy	sustain pea - Iwi and co	being maintained with adequate water levels to at formation and retain rare plant communities. mmunity have a strong connection to the wetland tive in its use, protection and restoration.	
Impact on the Vision & Strategy	In a restored condition the Moanatuatua Wetland would have a very high impact on giving effect to the Vision & Strategy at a local level.		VS = 20
Key threats to the feature that this	Key threat	Impact on the feature	
project addresses	Land drainage Fire	Lowers water levels in the bog causing peat oxidation and changes to vegetation. Could destroy existing native vegetation. Currently	
		no nearby seed sources to revegetate.	
Project goal/s	Within 2 years of project commencement there are structures in place to maintain water levels throughout the wetland.		
Priority works for funding	In order for t required to g between the	this project to proceed private landowners would be give consent for a weir to be installed in the drain ir property and the reserve. This project is ed to be undertaken as one complete piece of work.	

	Weir design and construction	
	- Site surveys to determine land and drain invert heights and	
	depth of peat (\$15,000).	
	- Weir design by engineer (\$10,000)	
	- Resource consent for the weir may be required (damming and	
	diverting water (\$5000)).	
	- Construction of up to two wooden weirs in the outlet drains of	
	the wetland (\$15,000 per weir).	
	Project management/Staffing/Incidentals	
	Staff to carry out landowner liaison, iwi engagement, Health and	
	Safety requirements, negotiate agreements, inspect works,	
	manage parts of the work as required (e.g. fencing or planting),	
	project reporting and financial management. Incidentals include	
	transport, office overheads, consumables and miscellaneous	
	professional fees.	
	This is estimated to be 30% of the direct project costs due to the	
	expected degree of consultation and negotiation required.	
Time lag for	If works were implemented over a 2-year period, it is estimated	L = 2
benefits to be	that the majority of the project benefits would be seen soon after	
realised	project completion.	
Effectiveness of	The Moanatuatua Wetland is in a degraded state with land	W = 0.3
works	drainage having resulted in significant drying of the margins and	
	changes in plant communities. Without this project it is expected	
	that there will be continued and potentially rapid deterioration	
	over the next 20 years, with the wetland at risk of losing	
	important values. If this project is successfully completed then	
	some significant improvement can be expected in wetland	
	condition over the next 20 years. However, this will likely need	
	to be supported by improvement and enforcement of rules around wetland drainage.	
Risk of technical	Moderate risk of project failure due to technical feasibility. Risks	F = 0.82
failure	are mostly related to failure of the weirs to maintain water levels	
	due to losses through other sources such as groundwater flows.	
	This is especially so at this site due to the substantial peat	
	shrinkage on adjacent farmland. However, similar weirs on the	
	outflows of nearby peat lakes have been successful in improving	
	minimum water levels at these sites.	
Adoptability	There may be significant challenges in getting key landowners to	A = 0.04
Αυοριαυπικ		A - 0.04
	agree to this work being undertaken. This would need to be	
	resolved during the early stages of project planning.	
Information	Average – based on site knowledge of local experts who are	
quality	experienced in constructing weirs in peat drainage systems.	
Knowledge gaps	On site investigations would be required to get a more accurate	
and response	estimate of costs and to inform a weir design and height.	
Socio-political	There is a high risk that the project will fail to meet its goals over	P = 0.37
risks	the long term due to socio-political risks. It would require co-	
	ordination of agencies, enforcement of existing rules and	
	approval of consent that may be challenging to obtain.	

Project duration (years)	2 years		
Up-front cost – total for implementation phase/project duration			C = 0.08
	Task	Cost (\$)	
	Site surveys to inform weir height and design	15,000	
	Weir design plans	10,000	
	Weir construction (wood and machinery) x 2	30,000	
	Resource consent	5000	
	Project management/staffing/incidentals (30%)	18,000	
	Total	78,000	



LISCLAIMER: While Wakato Regional Council has exercised all reasonable skill and care in controling the contents of this information. Waikato Regional Council accepts no liability in contract, fort or otherwise howsoever, for any boss, damage, injury or expense (whether direct, indirect or consequential) arising out of the provision of this information or its use by you.



A deep drain between a bog and adjoining farm.

WP 9			
Drievity High	Mangakara Strean		
Priority: High		BCR value	
Relevant unit goal(s)	Indigenous fish have access throughout the river catchments (except where natural barriers exist) and the catchment has an abundance of taonga species such as kōkopu, piharau, tuna, kōura and kāeo.		
Name of feature	Mangakara Stream, Te Pahu		
Brief description of feature	A 3.7km long stream flowing (near Grey Road, Te Pahu) to predominantly pastoral farm		
	This waterway was identified for native freshwater specie it has been identified by Ma for piharau. There are oppo abundance and diversity by		
Desired state to	increased and high quality fi	sn nabitat. cclude stock from its entire length. It	
achieve the Vision & Strategy	 has a well vegetated riparian margin along its entire length that provides erosion protection, shade and shelter. Native fish are abundant and the full range of species expected to be found in the waterway can be found there. There are no manmade barriers to native migratory fish. The stream is swimmable, fishable and has access for recreation. Iwi and communities have a strong connection to the stream and are active in its use, protection and restoration. 		
Value of the feature	In a restored condition the Mangakara Stream, Te Pahu, would have a high impact on giving effect to the Vision & Strategy at a local level.		VS = 1.5
Key threats to the feature that this			
project addresses	Key threat	Impact on the feature	
	Stock access to the stream	Reduced water quality and destruction of riparian vegetation.	
	Vegetation clearance	Reduced cover, habitat and food (invertebrates) for native fish species.	
	Culverts and crossings that are a barrier for native fish	Native fish unable to access upstream areas.	
Project goal/s	 Within 5 years of the project commencing: The full 3.7km length of Mangakara Stream is fenced to exclude stock and has a riparian margin (at least 5m wide) vegetated with predominantly native plant species. All manmade barriers to fish migration are remedied. 		
Priority works for funding	Suggested works could be in or private citizens (using cor		

		1
	project could be undertaken as a whole, or in multiple smaller components.	
	 Riparian management Undertake up to 6km of riparian fencing to a standard of at least 5 wires (2 electric) and set back at least 5m from the top of the streambank (\$48,000). Include adjoining wetland areas within the riparian fencing. Undertake native riparian planting at 1.5m spacing. Based on the assumption that 80% of the riparian margin requires planting, approximately 2.4ha of native planting is required at a cost of \$37,551 per hectare (\$90,124). 	
	Fish barriers Determine the location and type of barriers to fish passage. It is estimated that there are two barriers to fish passage (Grey Road culvert and potentially a farm crossing) on this watercourse. Undertake works to remedy fish barriers (\$10,000).	
	Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees.	
	This is estimated to be 20% of the direct project costs.	
Time lag for benefits to be realised	If works were implemented at an even pace over a 5-year period, it is estimated that the majority of the project benefits would be seen approximately 3.5 years after project completion.	L = 8.5
Effectiveness of works	The Mangakara Stream has its headwaters in native bush and is currently in good condition with some of the Vision & Strategy desired state aspects already being met, including being swimmable and fishable. Condition is not expected to signficantly decline or improve over the next 20 years in the absence of this project. However, if this project is successfully completed then the Mangakara Stream is expected to be in excellent condition and very close to desired state in 20 years' time, with aspects related to fish habitat and passage and stock exclusion all being addressed.	W = 0.3
Risk of technical failure	Risks are mostly related to establishment of plantings. There is a low risk of project failure due to technical feasibility.	F = 0.92
Adoptability	It is estimated that about half of landowners would adopt the works if they were fully incentivised. The extent of the fencing setbacks may be a challenge in terms of uptake. If there is already fencing close to the streambank in places (i.e. with a narrow riparian margin) landowners may be unwilling to move fences back to allow room for native planting.	A = 0.5

Information quality	Poor – riparian management requir	rements based predominantly	
	on review of aerial photography. Limited knowledge regarding		
	the location of fish migration barrie	ers.	
Knowledge gaps	It is unknown specifically how much	h fencing already exists. This	
and response	would need to be established as pa	rt of the project planning and	
	costings confirmed accordingly. Location of fish barriers would		
	need to be determined in the early	stages of the project.	
Socio-political risks	Low risk that the project will fail to meet its goals over the long		P = 0.85
	term due to socio-political risks.		
Project duration	5 years		
(years)			
Up-front cost –			C = 0.18
total for	Task	Cost (\$)	
implementation phase/project	Riparian fencing (6km)	48,000	
duration	Native planting (2.4ha)	90,124	
	Remedy of fish barriers	10,000	
	Project management/staffing/incidentals (20%)	29,624	
	Total	177,748	





An unfenced section of Mangakara Stream,



A section of Mangakara Stream where it is recommended fences be moved back and native riparian planting undertaken.

			1
WP 10	Mangauika Stream	fish habitat rehabilitation	
Priority: Medium		BCR value	
Relevant unit goal(s)	Indigenous fish have access throughout the river catchments (except where natural barriers exist) and the catchment has an abundance of taonga species such as kōkopu, piharau, tuna, kōura and kāeo.		
Name of feature	Mangauika Stream, Pirongi	a	
Brief description of feature	A 9km long stream flowing Te Tahi Road (and the wate at Pirongia village. The lan predominantly pastoral far vegetation.		
	This waterway was identifie habitat for native freshwat bullies and it has been ider historic fishing area for pih There are opportunities to diversity by remediating ba high quality fish habitat.		
Desired state to achieve the Vision & Strategy	 The stream is fenced to exclude stock from its entire length. It has a well vegetated riparian margin along its entire length that provides erosion protection, shade and shelter. Native fish are abundant and the full range of species expected to be found in the waterway can be found there. There are no manmade barriers to native migratory fish. The stream is swimmable, fishable and has access for recreation. Iwi and communities have a strong connection to the stream and are active in its use, protection and restoration. 		
Impact on Vision & Strategy	In a restored condition the Mangauika Stream, Pirongia, would have a high impact on giving effect to the Vision &		VS = 1.5
Kow throats to the	Strategy at a local level.		
Key threats to the feature that this	Key threat	Impact on the asset	
project addresses	Lack of riparian cover and associated fish habitat	Reduced habitat for adult fish.	
	Stock access to the stream	Reduced water quality and destruction of riparian vegetation.	
	Vegetation clearance	Reduced cover, habitat and food (invertebrates) for native fish species.	

	Culverts and crossings that are a barrier for native fish	
Project goal/s	 Within 5 years of the project commencing: The full 9km length of Manguika stream is fenced to exclude stock and has a riparian margin (at least 5m wide) dominated by native plant species to assist in providing, food, shade, shelter and habitat for native fish. All manmade barriers to fish migration are remedied. 	
Priority works for funding	Suggested works could be implemented either by an organisation or private citizens (using contractors or their own labour). This project could be undertaken as a whole, or in multiple smaller components.	
	Riparian management for fish habitat purposes Carry out riparian fencing with a minimum 5m setback from the top of the streambank (at least 5 wire with 2 electric wires). Include adjoining wetland areas within the riparian fencing.	
	Undertake native riparian planting within the fenced area and associated weed control and maintenance.	
	Further investigation is required to determine the length of stream requiring treatment. However, based on aerial photographs and known information about the catchment it is estimated that 75% of the stream (6.75km stream length or 13.5km of streambank) remains to be fenced and planted.	
	Fencing – 13.5km at \$8/m (\$108,000).	
	Planting of a 13.5km riparian margin that is at least 5m wide equates to 6.75ha of planting at \$37,552 per hectare (\$253,476). This cost includes site preparation, plant purchase, planting labour and five releasing events.	
	Remedy fish barriers Investigate the locations of barriers to fish passage and undertake the required work to remedy these barriers. This is estimated to cost up to \$10,000 (based on remediation of two barriers). Actual costs will depend on the number and type of fish passage barriers that require remediation.	
	Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees.	
	This is estimated to be 25% of the direct project costs.	
--------------------------------------	---	----------
Time lag for benefits to be realised	If works were implemented at an even pace over a 5-year period, it is estimated that the majority of the project benefits would be seen approximately 3.5 years after project completion.	L = 8.5
Effectiveness of works	The Mangauika Stream is currently in moderate condition with some of the Vision & Strategy desired state aspects being met, including being swimmable at times and fishable. Condition is not expected to either decline or improve over the next 20 years in the absence of this project. However, if this project is successfully completed then the Mangauika Stream is expected to be in very good condition and closer to desired state in 20 years' time, with aspects related to fish habitat and passage and stock exclusion all being addressed. The stream travels through pastoral land over its entire extent and so this project will not fully address the potential impacts of this on water quality.	W = 0.3
Risk of technical failure	There is a low risk of project failure due to technical feasibility. Risks are mostly related to establishment of plantings. The risk of losing works due to flooding are mitigated somewhat by the proposed 5m setbacks for fencing and planting.	F = 0.92
Adoptability	It is estimated that about half of landowners would adopt the works if they were fully incentivised. The extent of the fencing setbacks may be a challenge in terms of uptake. If there is already fencing close to the streambank in places (i.e. with a narrow riparian margin) landowners may be unwilling to move fences back to allow room for native planting. This would need to be determined during the project planning phase and costs adjusted accordingly for moving of fences.	A = 0.5
Information quality	Poor – riparian management requirements based predominantly on aerial photography. Limited knowledge regarding the location of fish migration barriers.	
Knowledge gaps and response	It is unknown specifically how much fencing already exists. This would need to be established as part of the project planning. Location of fish barriers would need to be determined in the early stages of the project. The water reservoir is one known barrier but there may be another on the water reservoir access track.	
Socio-political risks	Low risk that the project will fail to meet its goals over the long term due to socio-political risks.	P = 0.85
Project duration (years)	5 years	

Up-front cost – total for implementation phase/project duration	cost – total		C = 0.46
	Description	Cost (\$)	
	Remedy fish barriers	10,000	
	Fencing (13.5km)	108,000	
	Native planting (6.75ha)	253,476	
	Project Management/staffing/incidentals (25%)	92,869	
	Total	464,345	



DISCLAIMER: While Waikato Regional Council has exercised all reasonable skill and care in controlling the contents of this information, Waikato Regional Council accepts no liability in contract, tort or otherwise howsoever, for any loss, damage, injury or expense (whether direct, indirect or consequential) arising out of the provision of this information or its use by you.



Sections of Mangauika Stream where further riparian fencing and planting is recommended.

WP 11		ion protection and remediation – hanga to Pirongia	
Priority: High	Otoro	BCR value	
Relevant unit goal(s)	River margins prone to significant erosion are managed to minimise erosion risk, whilst enhancing aquatic habitat and retaining the natural character of river systems. Riparian planting of preferably indigenous species is undertaken to stabilise riverbanks, reduce erosion and enhance terrestrial and aquatic biodiversity.		
		t waters within the catchment are ake food from in all places.	
Name of feature	Waipā River – Ōtorohang	a to Pirongia	
Brief description of feature	Wapa RiverOtoronaligation inorigiaThis is a 37km stretch of the Waipā main stem lined with mostly exotic nuisance vegetation with many specimens at maturity and frequent collapse into the bed. This instigates bank instability and sedimentation of the main channel. The river is deeply incised through this stretch.This area is historically significant to iwi with multiple historic pā sites in the vicinity and of pakanga (battles) during the		
	papakāinga for many cen with significant interests Water quality informatio indicates that the river he but not always, safe for s Pirongia it is safe for fishi unsatisfactory levels of E		
Desired state to achieve the Vision & Strategy	 A 37km stretch of river with stable, vegetated banks and where major erosion events are limited. A riparian margin at least 10m wide that is well vegetated with native plants and exotic plants where required to prevent erosion. The river is swimmable, fishable and has access for recreation. Iwi and community have a strong connection to the river and are active in its use protection and restoration. 		
Impact on Vision & Strategy	In a restored condition the Waipā River – Ōtorohanga to Pirongia reach – would have a very high impact on giving effect to the Vision & Strategy at a Waipā catchment level.		VS = 125
Key threats to the	Key threat	Impact on feature	
feature that this project addresses	Mass bank erosion events and ongoing bank scouring	Estimated to yield approximately 9500 tonnes of sediment per year to the Waipā River, excluding major flood events.	

Project goal/s	Within 15 years of project commencement:	
	- The river has stable banks and a continuous	
	vegetated (native and exotic for erosion control) 37km	
	margin along the reach from Ōtorohanga to Pirongia.	
	- Stock is excluded from 100% of the river.	
	 Sediment to the Waipā River over this stretch is reduced by 	
	15%.	
Priority works for	Suggested works could be implemented either by an	
funding	organisation or private citizens (using contractors or their	
	own labour). This project could be undertaken as a whole, or	
	in multiple smaller components.	
	River erosion protection and remediation	
	- It is estimated that about a third of this reach will require	
	vegetation management for erosion purposes. This	
	equates to 12km of river at \$40 per channel metre	
	(\$480,000). Note: this should not be undertaken all at once,	
	but rather staged so that areas can revegetate before	
	others are cleared.	
	- Disposal is estimated at 20% of removal costs (\$96,000).	
	 Re-fencing will be required where vegetation has been 	
	removed. Assume a 3-wire electric for 24km of riverbank	
	(\$134,000).	
	- Willow/poplar poles should be planted for initial stability,	
	at 10m intervals along this length (2400 poles is \$33,600).	
	- For long term stability of the riverbank, native vegetation	
	should also be planted in these areas with a 10m setback.	
	This would require 24ha of planting (\$901,248).	
	- 30 woody debris structures (using vegetation on site)	
	should be installed as habitat for fish. At a cost of \$1600	
	per structure this equates to \$48,000.	
	- This stretch of the Waipā main stem is estimated to require	
	10 erosion protection structures along its length at a cost	
	of \$30,000 per structure (\$300,000).	
	Activities such as willow removal, installation of erosion	
	protection structures, installation of woody debris and any	
	earthworks associated with these actions may require	
	resource consent from Waikato Regional Council. Council's	
	Integrated Catchment Management division hold an existing	
	consent for much of this type on work on this waterway and	
	therefore anyone proposing to undertake river management	
	works should discuss this with council staff during project	
	planning.	
	Project management/staffing/incidentals	
	Staff to carry out landowner liaison, iwi engagement, Health	
	and Safety requirements, negotiate agreements, inspect	
	works, manage parts of the work as required (e.g. fencing or	
	planting), project reporting and financial management.	
	planting), project reporting and infancial management.	

	Incidentals include transport, office overheads, consumables	
	and miscellaneous professional fees.	
	This is estimated to be 30% of the direct project costs.	
Time lag for benefits	If works were implemented at an even pace over a 15-year	L = 12.5
to be realised	period, it is estimated that the majority of the project benefits would be seen approximately 12-13 years after project commencement.	
Effectiveness of works	The Waipā River (Ōtorohanga to Pirongia) varies in condition over this reach, being moderate at Ōtorohanga and poor by the time it reaches Pirongia. As this river travels through this reach it is joined by some rivers and streams with very high sediment loads including the Moakurarua and Puniū. The river is not swimmable towards Pirongia, the banks are unstable in many places and stock have access to the river at a number of locations. The riverbanks are not well vegetated with native plants.	W = 0.05
	Some deterioration in the river is expected over the next 20 years in the absence of this project, with impacts of the upper catchment, and bank stability in the Waipā main stem likely to lead to further decline in water quality and habitat for fish. This decline is expected to be offset by the outcomes of this project which will improve aspects related to bank stability, stock exclusion and extent of native vegetation along the margins. Overall, however, the upper catchment impacts will still be the biggest factor in water quality through this reach and therefore this stretch of river will benefit from works being undertaken both locally and in the upper catchments that it receives water from. It is acknowledged that achieving the Vision & Strategy desired state will take longer than the 20 year horizon used for the purposes of the Restoration Strategy	
Risk of technical failure	Strategy. There is a moderate risk of project failure due to technical feasibility. Risks are mostly related to establishment of plantings or loss of works due to flooding and/or erosion before they are established. This would be minimised by the fencing setbacks being at least 10m, and by planting sterile willow poles to stabilise banks while native plantings establish. Erosion control structures and fish habitats should be designed and constructed by experienced practitioners to avoid exacerbating erosion and/or other negative impacts and to minimise risk of failure.	F = 0.87
Adoptability	It is estimated that almost half of landowners would adopt the works if they were fully incentivised. The extent of the fencing setbacks is likely to be a challenge in terms of uptake. In addition there are large sections of the river that are meandering and erosive in nature and likely to flood on a regular basis. Landowners may be reluctant to erect fences in these locations due to the potential maintenance costs. This	A = 0.45

	risk can be reduced by the larger setbacks and plantings. There are also some existing project reach that provide a good example of what can with larger riparian margins.		
Information quality	Average – estimates are based on aerial photo catchment riparian surveys and input from cat who are familiar with the reach and are workir landowners to help them undertake similar wo		
Knowledge gaps and response	Unknown specifically how much fencing alread would need to be established as part of the pro-	oject planning.	
Socio-political risks	Low risk that the project will fail to meet its go long term due to socio-political risks.	als over the	P = 0.85
Project duration (years)	15 years		
Up-front cost – total	1		C = 2.59
for implementation phase/project	Description	Cost (\$)	
duration	Erosion protection structures (10)	300,000	
	Fish habitats (30)	48,000	
	Native planting (24ha)	901,248	
	Vegetation management (12km)	480,000	
	Vegetation disposal	96,000	
	Poplar/willow poles (2400)	33,600	
	Fencing (24km)	134,000	
	Project management/staffing/incidentals (30%)	597,854	
	Total	\$2,590,702	





Waipā River – Ōtorohanga to Pirongia – showing managed areas of vegetation management and large setbacks (far side of river).



Waipā River – Ōtorohanga to Pirongia – showing areas susceptible to erosion.



Waipā River just upstream of Pirongia village. Areas of bank erosion and instability can be seen, and the impacts of high sediment loads from the upper catchment are evident.

WP 12	Tuna habitat rehabilitation within 7 Pūniu River oxbows		
Priority: High		BCR value	
Relevant unit goal(s)	There is a programme of restoration of pā tuna, other significant fishing compromising the natural range of		
	Where possible, the natural functio ephemeral wetland sites is restored		
Name of feature	Puniū River oxbows		
Brief description of feature	A collection of old oxbows along the are well connected to the river whil various vegetated states – some wi others with small remnants of nativ flood when the Puniū River floods a throughout most of the year.		
	This area is of tribal significance to I as Mangatoatoa, the same name he directly at the confluence of the Pu restoration of these oxbows to imp greatly enhance the ability of the m manuwhiri (visitors).		
Desired state to achieve the Vision & Strategy	 Oxbows provide valuable habitat there in abundance. All oxbows are well connected to opportunity to inundate when Wa Open water areas are excluded fr appropriate vegetation to assist in aquatic weed growth. Stands of willow remain in place to Iwi and communities have a stron and are active in their use, protect 		
Impact on Vision & Strategy	In a restored condition the Puniū River oxbows would have a high impact on giving effect to the Vision & Strategy at a local level.		VS = 2
Key threats to the feature that this			
project addresses	Key threat	Impact on the feature	
	Drainage, disconnection from the river, infilling with overburden and conversion to pasture	Loss of tuna (eel) habitat and loss of a unique feature in the landscape.	
Project goal/s	 Within 5 years of this project commencing: Oxbows are fenced to exclude stock Increase by 25% the overall area that inundates at least three times per year and retains water for at least three weeks following flood events. 		

	- A 5m buffer of native and exotic (poplars) plants is created around open water areas to provide shade to assist in reducing water weeds and providing a food source for tuna	
Priority works for funding	water weeds and providing a food source for tuna.Suggested works could be implemented either by an organisation or private citizens (using contractors or their own labour). This project could be undertaken as a whole, or in multiple smaller components.	
	Project plan development Each oxbow will need to have a more detailed works plan developed which provides a detailed design showing where work will be undertaken, ground levels for excavation (if applicable), expected inundation areas, planting and fencing areas. The cost of this will vary for each site but a cost of up to \$5000 has been estimated per site.	
	Increase habitat for tuna Where possible, undertake earthworks work in oxbows 1a, 1b, 1c, 1d, 1f and 1g to increase the area of land that has standing water during and after flood events, and remove weeds choking existing ponding areas. If required, improve connectivity to the river in all oxbows by installation of culverts and channels.	
	Undertake steps to improve flow within oxbow 1e – this may involve improving connectivity to the river. Avoid removing willows unless necessary to achieve desired area of open water.	
	Aquatic weed management Undertake a mix of native and exotic planting (poplars) around open water areas. The purpose of planting will be to assist in shading out water weeds and provide a food source for invertebrates.	
	Earthworks and planting The following estimates have been made around the work required:	
	Oxbow 1a – 3 days long reach excavator and a 6m long culvert (\$6310), 1 day crosscutter for selective pest tree removal (\$700), 620m long section of fencing (\$4960) and native planting (on average 5m wide), a row of exotic trees (e.g. poplar) planted every 15m to provide shade (\$12,757).	
	Oxbow 1b – 4 days earthworks with 12 tonne excavator and a 6m long culvert (\$6360), 1 day crosscutter for selective pest tree removal (\$700), 260m long section of fencing (\$2080) and planting (on average 5m wide), a row of exotic trees planted every 15m to provide shade (\$5349).	
	Oxbow 1c – 5 days long reach excavator for a 6m long culvert (\$9550), 400m long section of fencing (\$3200), native planting	

	(average 5m wide), a row of exotic trees every 15m to provide fast growing shade (\$8222).	
	Oxbow 1d – up to 20 days long reach excavator and a 6m long culvert (\$33850), 700m long section of fencing (\$5600), native planting (on average 5m wide), a row of exotic trees planted every 15m to provide fast growing shade (\$14,403).	
	Oxbow 1e – culvert installation if required (\$1050 for a 6m long culvert).	
	Oxbow 1f – 200m willow removal (\$6000), 4 days long reach excavator to excavate inundation area and install a 6m long culvert if required (\$7930), 400m fencing (\$1600) and native planting. A row of exotic trees planted 15m apart to provide fast growing shade (\$4115).	
	Oxbow 1g – 1 day long reach excavator and installation of culvert if required (\$3070), 700m long section of fencing (\$5600), natives tree planting (5m wide margin on average) and a row of exotic trees for shade planted at 15m spacing (\$14,403).	
	It is assumed that a 12 tonne excavator will move 200m ³ of soil per hour and that a long reach excavator will remove 150m ³ per hour.	
	Resource consent Resource consent costs may be required for some projects. A budget of \$5000 per site has been allowed for this. This assumes that consent applications may be lodged at different times for different oxbows. A budget of \$5000 per project has been provided for investigation and design.	
	Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees.	
	This is estimated to be 30% of the direct project costs.	
Time lag for benefits to be realised	If works were implemented at an even pace over a 5-year period, it is estimated that the majority of the project benefits would be seen within 1 year of project completion.	L = 5.5
Effectiveness of works	These oxbows are currently in a poor condition when compared to desired state. It is not expected that they will deteriorate significantly over the next 20 years if this project is not undertaken. However, if this project is successfully completed then it is expected that oxbow condition in 20 years will be significantly closer to the desired Vision & Strategy state than it is currently.	W = 0.4

	This project addresses the majority of aspirations for these	
	features.	
Risk of technical	There is a high risk of project failure due to technical feasibility.	F = 0.65
failure	Techniques are not well established or tested. Risks relate to	
	providing adequate flow and supply of water to the oxbows year	
	round, and preventing pest fish dominating the fish biomass at	
	these sites. Expert engineering advice should be sought in the	
	early stages of the project.	
Adoptability	It is estimated that almost half of landowners would adopt the	A = 0.45
	works if they were fully incentivised. There may be concerns about	
	reconnection of sites with the river and increased flooding.	
	However, site design should ensure that this is avoided. There	
	could also be reluctance to give up summer grazing areas to create	
	more open water habitat. Some sites have been contoured and re-	
	grassed to provide additional grazing. Early landowner	
	engagement will be important as part of project planning.	
	Average – recommendations are based on the judgement of a fish	
Information quality	expert with some local knowledge. Quantities of work required	
	are predominantly based on estimates made from aerial	
	photographs.	
Knowledge gaps and	Further investigation is required to determine what is feasible and	
response	practical at each oxbow site. More information is required about	
	each oxbow including current connectivity to the river, and	
	whether there is opportunity to improve connectivity and increase	
	the area and duration of inundation. This should be undertaken at	
	the early stages of project planning.	
	A detailed design needs to be carried out for each site and this	
	should be undertaken early in project implementation.	
Socio-political risks	Low risk that the project will fail to meet its goals over the long	P = 0.85
	term due to socio-political risks.	
Project duration	5 years	
(years)		

Up-front cost – total			C = 0.30
for implementation	Task	Total (\$)	
phase/project duration	Project plan development (up to \$5,000 per site)	35,000	
	Oxbow 1a physical works	24,727	
	Oxbow 1b physical works	14,489	
	Oxbow 1c physical works	20,972	
	Oxbow 1d physical works	53,853	
	Oxbow 1e physical works	1,050	
	Oxbow 1f physical works	19,645	
	Oxbow 1g physical works	23,073	
	Resource Consent	35,000	
	Project management/staffing/incidentals (30%)	68,342	
	Total	296,151	



DISCLAIMER: While Wakato Regional Council has exercised all reasonable skill and care in controling the contents of this information or its use by you.

WP 13	Ngakoaohia Stream (and selected tributaries) fish	
Priority: Medium	habitat rehabilitation	BCR value
Relevant unit goal(s)	Indigenous fish have access throughout the river catchments (except where natural barriers exist) and the catchment has an abundance of taonga species such as kōkopu, piharau, tuna, kōura and kāeo.	
Name of feature	Ngakoaohia Stream and selected tributaries (flowing from Pirongia mountain near Ngutunui)	
Brief description of feature	A 26km long stream network flowing from Mt Pirongia in the vicinity of Ngutunui to join the Waipā River approximately 7km kilometres upstream of Pirongia village. Streams within the network include Mangati Stream, Whakarautawa Stream, Mangakiekie Stream and Pekanui Stream. The land use either side of the stream is predominantly pastoral farming or native bush remnants.	
	The Pirongia area has long been an important place for tāngata whenua. Its vast forests and waters were a significant food bowl for its people. Pirongia was named by Kuahupeka not long after the arrival of the Tainui waka in Kāwhia. Its full name is "Pirongia-te-aroaro-o-Kahu". Kahupeka left the Kāwhia area to traverse inland.	
	These waterways have been identified as priorities as they are known to have populations of native fish species and these are expected to respond well to further habitat enhancement work.	
Desired state to achieve the Vision & Strategy	 Within 15 years of the project commencing: Stock is excluded from all waterways within the catchment. The stream network has a well vegetated native riparian margin along its entire length (at least 5m wide) Potential manmade barriers to fish passage have been remedied. 	
	 Native fish are abundant and there is a wide diversity of species present including non-climbing species. There are no manmade barriers to native migratory fish. Waterways are swimmable, fishable and have access for recreation. Iwi and communities have a strong connection to the streams and are active in their use, protection and restoration. 	
Impact on Vision & Strategy	In a restored condition the Ngakoaohia Stream and selected tributaries flowing from Pirongia mountain would have a very high impact on giving effect to the Vision & Strategy at a local level.	VS = 8

Key threats to the			
feature that this	Key threat	Impact on the asset	
project addresses	Lack of riparian cover and associated fish habitat	Reduced habitat for adult fish.	
	Stock access to the stream	Reduced water quality and destruction of riparian vegetation.	
	Vegetation clearance	Reduced cover, habitat and food (invertebrates) for native fish species.	
	Culverts and crossings that are a barrier for native fish	Native fish unable to access upstream areas.	
Project goal/s	and has a riparian margin which is vegetated with shade and enhance habin	twork is fenced to exclude stock n of at least 5m wide on both sides plant species to provide stream tat for adult native fish. tive fish migration are identified	
Priority works for funding	Suggested works could be implemented either by an organisation or private citizens (using contractors or their own labour). This project could be undertaken as a whole, or in multiple smaller components.		
	the top of the streambank	vith a minimum 5m setback from (5 wire fence, 2 electric wires). areas and forest remnants within	
	stream requiring treatment photographs and known in estimated that 50% (13km) fenced (or fence upgraded)	uired to determine the length of t. However, based on aerial formation about the catchment it is of the stream remains to be). This equates to a total fence) at an estimated \$8 per metre	
	carry out associated weed plant establishment. - Assume 50% (26km) of st This equates to a planting of \$37,552/ha (\$488,176	blanting along the waterway and control and maintenance for native treambanks require native planting. g area of 13ha at an estimated cost). Includes site preparation, plant	
	purchase, planting labou Remediation of fish barrie	r and five releasing events. rs	

	works if they were fully incentivised. The extent of the fencing setbacks may be a challenge in terms of uptake. If there is already fencing close to the streambank in places (i.e.	
Risk of technical failure Adoptability	 Low risk of project failure due to technical feasibility. Risks are mostly related to establishment of plantings or loss of works due to flooding. It is estimated that almost half of landowners would adopt the 	F = 0.87 A = 0.45
	Strategy desired state aspects already being met, including being swimmable and fishable. Condition is expected to decline over the next 20 years in the absence of this project. However, if this project is successfully completed then these sites are expected to improve and be closer to desired state with aspects related to fish habitat and passage and stock exclusion all being addressed.	
Effectiveness of works	completion. The Ngakoaohia Stream and selected tributaries are currently in moderate to good condition with some of the Vision &	W = 0.15
Time lag for benefits to be realised	If works were implemented at an even pace over a 10-year period, it is estimated that the majority of the project benefits would be seen approximately one year following project	L = 11
	planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees. This is estimated to be 30% of the direct project costs.	
	Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or	
	It is also estimated that there are a large number of fish barriers on private land, particularly along raceways and farm tracks (possibly as many as 12). The estimated cost for remediation of fish barriers is up to \$5000 per barrier. Resource consent may be required for remediation of fish barriers and the cost of this should be covered by the cost estimate provided for remediation of fish barriers.	
	 The following culverts/crossings are thought to provide a barrier or partial barrier to fish passage: Culvert where Pekanui Road crosses Pekanui Stream. Culvert where Mangiti Road crosses Mangakiekie Stream. Two culverts (in two locations) where Mangati Road crosses Mangati Stream. Culvert where Kiwi Road crosses Ngakoaohia Stream. 	
	Investigate the locations of barriers to fish passage and undertake the required work to remedy these barriers. Remediation options should follow the recommendations of a freshwater fish ecologist.	

	with a narrow riparian margin) landowners m	, .	
	to move fences back to allow room for native planting.		
Information quality	Poor – riparian management requirements are based		
	predominantly on review of aerial photograph	, , ,	
	management requirements are based on som	e limited local	
	knowledge but predominantly on aerial photo	• • •	
	layers for fish barriers and fish species predict	ability.	
Knowledge gaps and	It is unknown how much fencing already exist		
response	it is to the stream edge. Detailed fencing requ		
	need to be determined in the early stages of t	he project.	
	It is also unknown exactly how many barriers		
	there are along the stream and whether land		
	willing to remedy such barriers. This will need		
	determined during the project planning phase		
Socio-political risks	Low risk that the project will fail to meet its g	oals over the	P = 0.85
	long term due to socio-political risks.		
Project duration (years)	10 years		
Up-front cost – total			C = 1.02
for implementation	Task	Cost (\$)	
phase/project duration	Fencing (26km)	208,000	
	Native planting (13ha)	488,176	
	Remediation of fish barriers	85,000	
	Project management/staffing/incidentals (30%)	234,352	
	Total	1,015,528	



WP 14	Moakurarua integrated catchment programme	
Priority: Very high	Moakurarua integrateu catchment programme	BCR value
Relevant unit goal(s)	The appropriate management of steep and erosion prone land is promoted and incentivised.	
	River margins prone to significant erosion are managed to minimise erosion risk, whilst enhancing aquatic habitat and retaining the natural character of river systems.	
	Riparian planting of preferably indigenous species is undertaken to stabilise riverbanks, reduce erosion and enhance terrestrial and aquatic biodiversity.	
	Water quality is such that waters within the catchment are swimmable and safe to take food from in all places.	
	Land uses are being adapted to match the capability of the land.	
	The catchment has an interconnected network of healthy, indigenous ecosystem types (forest, shrubland, wetlands, lakes, river and stream habitats and margins) supporting native flora and fauna.	
	Indigenous fish have access throughout the river catchments (except where natural barriers exist) and the catchment has an abundance of taonga species such as kōkopu, piharau, tuna, kōura and kāeo.	
Name of feature Brief description of feature	Moakurarua subcatchment A 14,974ha catchment in the upper Waipā with a total stream network of 277km. 34% of the catchment is in indigenous forest. Moakurarua Stream starts in the hill country south of Honikiwi and flows north to join the Waipā River approximately 7km upstream of Pirongia. The predominant land use within the catchment is pastoral farming (58% of the total area). Approximately 6000ha of land is LUC 6e or 7 in pasture and the catchment has been identified as a priority sediment catchment in the Waipā Catchment Plan and through the Healthy Rivers Plan Change.	
	A 62km long stream network consisting of Moakurarua Stream and selected tributaries flowing from hill country to the west has been identified as a priority for native fish. Within this, a 27km stretch of the main stem of the Moakurarua Stream upstream of the Waratah piggery and an 8km stretch of the Oamaru Stream have been identified as priorities for river management through bank stabilisation. The top 6km of the Moakurarua stretch is a	

Desired state to	fully fenced and lacks co caused by stock access, l events. The next 21km of and highly erodible bank high. Lateral bank erosion stretch of the stream. The Oamaru Stream has estimated that there is 5 required along this streat Upper Moakurarua fores within the top 30% of bio River catchment (based marae with significant co area. A subcatchment where l	st fragments have been identified odiversity priorities in the Waikato on representativeness). There are 9 ultural and historical interests in this and use matches capability and with	
achieve the Vision & Strategy	 a stable stream network that has a well vegetated riparian margin along its entire length (at least 5m wide) to assist in providing erosion protection and shade, shelter. Native and taonga species are abundant and there is a wide diversity of species present The river is swimmable, fishable, safe for gathering kai, and has access for recreation. Iwi and communities have a strong connection to the river 		
Impact on Vision & Strategy	In a restored condition t would have a very high i	protection and restoration. he Moakurarua subcatchment mpact on giving effect to the Vision	VS = 275
Key threats to the	& Strategy at a Waipā ca	Impact on feature	
feature that this project addresses	Hill country erosion	Estimated to yield more than 10,000 tonnes of sediment per year to the Waipā River	
	Riverbank erosion	Estimated to yield approximately 2300 tonnes of sediment per year to the Waipā River, excluding major flood events.	
	Stock access to the stream	Reduced water quality and destruction of riparian vegetation.	
	Lack of riparian cover and associated fish habitat	Reduced habitat for adult fish.	
Project goal/s		ct commencement: he Moakurarua Stream is stable, ck and vegetated along its entire	

	 There is a 25% reduction in suspended sediment in the Moakurarua Stream 	
	- A 62km stream network is established that is stable,	
	excluded to stock and has a vegetated riparian margin of	
	predominantly native plant species (at least 5m wide) to	
	enhance habitat for native fish species, especially tuna,	
	piharau, kōura and kōkopu.	
	- Native forest remnants and wetlands identified are fully	
	fenced to exclude stock and native regeneration occurs	
	naturally within these areas.	
Priority works for	Suggested works could be implemented either by an	
funding	organisation or private citizens (using contractors or their	
	own labour). This project could be undertaken as a whole,	
	or in multiple smaller components.	
	Hill country soil conservation	
	- 665ha LUC 6e managed with open space pole planting at	
	\$3000 per hectare (\$1,995,000).	
	- 665ha LUC 6e managed with plantation species (e.g. pine	
	or mānuka) at \$3000 per hectare (\$1,995,000).	
	- 131km of fencing the managed LUC 6e land at \$20 per	
	metre (8-wire and batten) (\$2,620,000).	
	- 647ha LUC 7 managed with plantation species (e.g. pine	
	or mānuka) at \$3000 per hectare (\$1,941,000).	
	- 91km of fencing managed LUC 7 land at \$20 per metre (8-	
	wire and batten) (\$1,820,000).	
	- 22ha reducing sediment to waterways outside LUC class	
	6e, 7 and 8 land at \$5000 per ha (e.g. dewatering, retiring	
	seepages, etc) (\$110,000).	
	- 60 hunter days per year for 3 years of goat control while	
	plantings on 6e and 7 establish. Control carried out over a	
	6000ha area.	
	- 38km fencing existing indigenous forest cover at \$25m (8-	
	wire and batten) (\$950,000).	
	Riparian Management of rivers/streams for fish habitat	
	and soil conservation purposes	
	- Carry out riparian fencing along 72km of streambank	
	(31km of stream length) with a minimum 5m setback from	
	· · · · · · · · · · · · · · · · · · ·	
	the top of the streambank (at least 5 wire with 2 electric wires) at an actimated part of 68 per metro ($6776,000$)	
	wires) at an estimated cost of \$8 per metre (\$576,000).	
	Include adjoining wetland areas within the riparian	
	fencing.	
	- Undertake a mix of native and exotic soil conservation	
	riparian planting within the fenced area (where it doesn't	
	exist naturally), estimated to be 36ha of planting, and	
	associated weed control and maintenance (\$1,351,872)	
	River management for large scale erosion	
	21km stretch in the mid-section of the Moakurarua and 5km	
	of the Oamaru Stream requires hard and soft engineering	

failure	feasibility. It is important that appropriately experienced practitioners are undertaking/advising on the more technical aspects of the project such as river erosion control structures. There are risks related to establishment of plantings or loss of works due to flooding, however techniques are well established and have been used previously on this and other local streams. River erosion structures should be designed by an appropriately qualified practitioner.	
Risk of technical	expected that over the next 20 years there will be a deterioration in the condition of the catchment in the absence of this project. It is acknowledged that achieving the Vision & Strategy desired state will take longer than the 20 year horizon used for the purposes of the Restoration Strategy. However, works included in this project address many of the threats to the feature and it is anticipated that if the project is fully completed it would offset anticipated decline and make significant progress with respect to achieving the Vision & Strategy state in 20 years' time. There is a moderate risk of project failure due to technical	F = 0.82
Effectiveness of works	commencement. The Moakurarua subcatchment is in very poor to poor condition compared with the desired state with few of the Vision & Strategy aspirations currently being met. It is	W = 0.4
Time lag for benefits to be realised	This is estimated to be 30% of the direct project costs. If works were implemented at an even pace over a 15-year period, it is estimated that the majority of the project benefits would be seen approximately 13 years after project	L = 12.5
	Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees.	
	completion of works (\$420,000). Activities such as willow removal, installation of erosion protection structures, installation of woody debris and any earthworks associated with these actions may require resource consent from Waikato Regional Council. Council's Integrated Catchment Management division hold an existing consent for much of this type on work on this waterway and therefore anyone proposing to undertake river management works should discuss this with council staff during project planning.	
	structures to protect banks from mass erosion. Estimated at \$20,000 per km. This cost includes fencing and planting post	

Adoptability	It is estimated that about a third of landowners would adopt the works if they were fully incentivised. The extent of the fencing setbacks may be a challenge in terms of uptake. If there is already fencing close to the streambank in places (i.e. with a narrow riparian margin) landowners may be unwilling to move fences back to allow room for native planting. There are large sections of stream that are meandering and erosive in nature and likely to flood on a regular basis. Landowners may be unwilling to erect fences in these location due to the high maintenance costs. Fencing is also difficult in places due to the steepness of the land. Uptake of management of LUC class 6e and 7 land may be low however there are some existing projects along this reach that provide a good example of what can be achieved through farm planning. Early community engagement and identifying key farmers will be very important for the success of this project.	A = 0.36
Information quality	Good – estimates are based on modelled information and input from catchment officers who have experience working in the subcatchment, know the river well and are working with landowners to help them undertake similar works.	
Knowledge gaps and response	It is unknown exactly how much fencing already exists and estimates are based on Waipā catchment riparian surveys. It is also unknown how close existing fences are to the stream edge. Estimates of LUC classes 6e, 7 and 8 come from a desktop exercise. Farm scale information will need to be gathered as part of this project.	
Socio-political risks	Low risk that the project will fail to meet its goals over the long term due to socio-political risks. Opportunities to have this work incentivised should be greeted positively.	P = 0.85
Project duration (years)	15 years	

Up-front cost – total			C = 18.16
for implementation	Task	Cost (\$)	
phase/project duration	26km river erosion control	520,000	
	Pole planting erosion prone LUC class 6e land (665ha)	1,995,591	
	Plantation species on erosion prone LUC class 6e land (665ha)	1,995,591	
	Fencing managed LUC class 6e land (131km)	2,645,023	
	Plantation species on LUC class 7 land (647ha)	1,939,516	
	Fencing managed LUC class 7 land (91km)	1,813,778	
	Treating erosion outside LUC class 6e, 7 and 8 land (22ha)	110,000	
	Streambank fencing (72km)	576,000	
	Riparian planting river/streams (36ha)	1,351,872	
	Fencing existing indigenous vegetation (38km)	950,000	
	Goat control on 6e and 7	73,440	
	Project management/staffing/incidentals (30%)	4,191,243	
	Total	\$18,162,054	





Examples of mass earth movement in the Moakurarua catchment.



A mixture of high erosion class land and some remnant vegetation in the Moakurarua catchment.



Large scale riverbank erosion on the Moakurarua Stream.



Resulting downstream sedimentation following a large weather event in the Moakurarua catchment.

WP 15	Tuna habitat rehabilitation within 10 Waipā River oxbows		
Priority: High			BCR value
Relevant unit goal(s)	There is a programme of restoration, enhancement and protection of pā tuna, other significant fishing sites and fish habitat without compromising the natural range of species.		
	Where possible, the natural functioni other ephemeral wetland sites is rest		
Name of feature	Waipā River oxbows		
Brief description of feature	This project focuses on a collection of historic oxbows along the Waipā River between Pirongia and Ōtorohanga. Some of these are well connected to the river while some are not. They are in various vegetated states – some with dense willow canopy and others with small remnants of native vegetation. All of the oxbows flood when the Waipā River floods and many retain water throughout most of the year.		
	These have been identified by fish ex for tuna and there are opportunities areas for tuna habitat. The enhancen also support the historical relationshi whenua and its natural resources.	to further enhance these nent of this habitat would	
Desired state to achieve the Vision &	- Oxbows provide valuable habitat for tuna and tuna are found there in abundance.		
Strategy	 All oxbows are well connected to the maximum opportunity to inundate are high. Open water areas are excluded from 		
	appropriate vegetation to assist in t aquatic weed growth. - Stands of willow remain in place to	the prevention of dense	
	 Iwi and communities have a strong and are active in their use, protection 	connection to the oxbows	
Impact on Vision & Strategy	In a restored condition the Waipā River oxbows would have a very high impact on giving effect to the Vision & Strategy at a local level.		VS = 3
Key threats to the		г	
feature that this	Key threat	Impact on the feature	
project addresses	Drainage, vegetation clearance and the filling of old oxbows with overburden and conversion to pasture.	Loss of tuna habitat and loss of a unique feature in the landscape.	
Project goal/s	Within 5 years of this project comme - Oxbows are fenced to exclude stocl		

	 Increase by 25% the overall area that inundates at least three times per year and retains water for at least three weeks following flood events. 	
	- A 5m buffer of native and exotic (poplars) plants is created around open water areas to provide shade to assist in	
	reducing water weeds and providing a food source for tuna.	
Priority works for	Suggested works could be implemented either by an	
funding	organisation or private citizens (using contractors or their own labour). This project could be undertaken as a whole, or in multiple smaller components.	
	Project plan development Each oxbow will need to have a more detailed works plan developed which provides a detailed design showing where work will be undertaken, ground levels for excavation (if applicable), expected inundation areas, planting and fencing areas. The cost of this will vary for each site but a cost of up to \$5000 has been estimated per site.	
	Increase habitat for tuna Ensure there is good connectivity between the Waipā River and the oxbows. If required improve connectivity to the river through installation of culverts and channels.	
	Where possible, undertake earthworks in oxbows 2a to 2h to increase the area of land that has standing water during and after flood events, remove any dense areas of aquatic vegetation encroaching on existing ponding areas.	
	Undertake steps to improve flow within oxbows 2i and 2j (see map) – this may involve improving connectivity to the river. Limit willow removal as this provides habitat for tuna. Any willow removal should only be undertaken above water to enable machinery access to increase the size of inundation areas.	
	Aquatic weed management Undertake a mix of native and exotic planting (poplars) at oxbows 2a and 2h to provide shade over the pond area.	
	Earthworks and planting The following estimates have been made around the amount of earthworks and planting required but further investigation and planning is required.	
	Oxbow 2a – costings include earthworks and installation of up to four 450mm diameter, 6m long culverts or similar to improve connectivity (and some additional excavator time) (\$5130), 1ha of selective willow herbicide control to increase the area of open water (\$3800), and 1130m fencing to exclude stock (\$9040).	

Oxbow 2b - Costings allow for earthworks to increase area and/or depth of standing water and improve connectivity (2 culverts and 2 digger days \$5440). Selective herbicide control of willow to increase the area of open water (\$1900). 850m fencing (\$6800), 200m of native planting with a 5m wide riparian margin (\$3995). Oxbow 2c – costings allow for earthworks to increase area	
and/or depth of standing water and improve connectivity. Up to four culverts and 2 digger days (\$7,240). Selective herbicide control of willow to increase the area of open water (\$1900), 441m fencing (\$3528), and 200m of native planting with a 5m wide riparian margin (\$3995).	
Oxbow 2d – create permanent ponding area approximately 130m x 30m (4 days digger time using a long reach digger \$6880), 320m fencing (\$2560), 320m native planting around perimeter, a row of exotic trees on northern side every 15m to provide fast growing shade (\$6448), and culverts to connect to the river (\$1800).	
Oxbow 2e – create permanent ponding area approximately 6000m ² x 2m deep (200m long x 30m wide)(10 days with long reach digger \$16,600) and connect to river (with culverts if required, \$1800), 750m fencing (\$6000) and native/exotic planting with an average riparian margin of 5m wide (\$10,008).	
Oxbow 2f – increase the size of the permanent ponding area by 30m x 50m (3 days with a 12 tonne excavator \$4050) and connect to river with culverts if required (\$1800). Undertake 500m fencing (\$4000) and native planting (\$3200) and additional willow/weed control if required (\$2600).	
Oxbow 2g – improve connectivity to river with two culverts (1 day earthworks \$3330). Selective willow control (x-tree basal) to increase the area of open water (\$3800). Oxbow fencing 1.6km (\$13,000). Some native planting along inlet/outlet (two rows 320m at \$3796).	
Oxbow 2h – improve connectivity to the Waipā River (two culverts \$1800), increase area of open water (4 long reach digger days \$6880). Selective ground based willow removal (\$2600), 880m of fencing (\$7040) and a small amount of native planting in open areas (\$3796).	
Oxbow 2i – investigate connecting this old oxbow to the river at the upstream end. Allow earthworks two days and two 6m long culverts (\$5440). Assume mostly fenced (\$1600 allocated for fencing), and selected ground based willow control if required (\$2790).	

Г			
	Oxbow 2j – investigate connecting to river at upstream end. Allow earthworks two days and two 6m long culverts (\$5440). Assume mostly fenced (\$1600 allocated for fencing), and selected ground based willow control if required (\$2790). Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees.		
	This is estimated to be 30% of the direct project costs.		
Time lag for benefits	If works were implemented at an even pace over a 5-year	L = 5.5	
to be realised	period, it is estimated that the majority of the project benefits would be seen within 1 year of project completion.	_ 0.0	
Effectiveness of works	These oxbows are currently in a poor-moderate condition when compared to desired state. It is expected that they will deteriorate slowly over the next 20 years if this project is not	W = 0.25	
	undertaken. However, if this project is successfully completed then it is expected that oxbow condition in 20 years will be significantly closer to the desired Vision & Strategy state than it		
	is currently. This project addresses the majority of aspirations for these features.		
Risk of technical failure	There is a high risk of project failure due to technical feasibility. Techniques are not well established or tested. Risks relate to providing adequate flow and supply of water to the oxbows year round, and preventing pest fish dominating the fish biomass at these sites. Expert engineering advice should be sought in the early stages of the project.	F =0.7	
Adoptability	It is estimated that about half of landowners would adopt the works if they were fully incentivised. There may be concerns about reconnection of sites with the river and increased flooding. However, site design should ensure that this is avoided.	A = 0.54	
Information quality	Average – recommendations are based on the judgement of a fish expert with some local knowledge. Quantities of work required are predominantly based on estimates made from aerial photographs.		
Knowledge gaps and response	Further investigation is required to determine what is feasible and practical at each oxbow site. More information is required about each oxbow including current connectivity to the river, and whether there is opportunity to improve connectivity and increase the area and duration of inundation. This should be undertaken at the early stages of project planning.		
	A detailed design needs to be carried out for each site and this should be undertaken early in project implementation.		
Socio-political risks	Low risk that the project will fail to meet its goals over the long term due to socio-political risks.		P = 0.85
-----------------------------	--	------------	----------
Project duration (years)	5 years		
Up-front cost – total			C = 0.37
for implementation	Task	Total (\$)	
phase/project duration	Design plan development (up to \$5,000 per site)	50,000	
	Resource consent (\$5,000 per site)	50,000	
	Oxbow 2a physical works	17,970	
	Oxbow 2b physical works	18,135	
	Oxbow 2c physical works	16,663	
	Oxbow 2d physical works	17,688	
	Oxbow 2e physical works	34,488	
	Oxbow 2f physical works	15,650	
	Oxbow 2g physical works	23,926	
	Oxbow 2h physical works	22,116	
	Oxbow 2i physical works	9,830	
	Oxbow 2j physical works	9,830	
	Project management/staffing/incidentals (30%)	85,888	
	Total	372,184	







Photo of Waipā River oxbows 2a and 2b.



Photo of oxbows 2g and 2h.



Oxbows 2i and 2j.

WP 16	Mangatutu River erosion protection, remediation and	
Priority: Very high	management and fish habitat rehabilitation	BCR value
Relevant unit goal(s)	River margins prone to significant erosion are managed to minimise erosion risk, whilst enhancing aquatic habitat and retaining the natural character of river systems.	
	Riparian planting of preferably indigenous species is undertaken to stabilise riverbanks, reduce erosion and enhance terrestrial and aquatic biodiversity.	
	Water quality is such that waters within the catchment are swimmable and safe to take food from in all places.	
	Indigenous fish have access throughout the river catchments (except where natural barriers exist) and the catchment has an abundance of taonga species such as kōkopu, piharau, tuna, kōura and kāeo.	
Name of feature	Mangatutu River	
Brief description of feature	A 20km reach of the Mangatutu River from Puniū to Wharepuhanga Road. About 25% of this reach has had some work undertaken involving erosion control and native and exotic plantings. The river has a moderate gradient with a gravel and stony bed. Banks range from 1m to 3m high across the reach. Riverbank erosion along this reach generally occurs during high flow events and is prevalent where there is no stabilising vegetation – occurring mainly on outside bends. There is lateral bank erosion in the upper reach and bank slumping in the lower reach.	
	According to Waikato Regional Council monitoring results the Mangatutu River at Walker Road bridge is safe for swimming some but not all of the time.	
Desired state to achieve the Vision & Strategy	 A 20km reach of river with stable, vegetated banks and where major erosion events are limited. A riparian margin that is well vegetated with native plants (at least 5m wide) and exotic plants where required to prevent erosion. There is increased in-stream structure (at least 10 woody structures per kilometre) to provide habitat for fish, particularly tuna and piharau. The river is swimmable, fishable and has access for recreation. Iwi and communities have a strong connection to the river and are active in its use, protection and restoration. 	
Impact on Vision & Strategy	In a restored condition the Mangatutu River would have a high impact on giving effect to the Vision & Strategy at a Waipā catchment level.	VS = 80

Key threats to the	Kouthrast	Import on facture	
feature that this	Key threat	Impact on feature	
project addresses	Riverbank erosion	Estimated to yield approximately 1300 tonnes per year of sediment to the Waipā River, excluding major flood events.	
	Stock access to the stream	Reduced water quality and destruction of riparian vegetation.	
	Lack of riparian cover and associated fish habitat	Reduced habitat for adult fish.	
	Lack of woody debris and structures within the stream channel	Reduced habitat for adult native fish and trout.	
Project goal/s	vegetated (at least 5m providing increased sh - There are 10-15 struct protection against ero fish, particularly tuna.	ct commencement: langatutu River is stable, fenced and setback) along its entire length ade, shelter and food for native fish. ures per kilometre that provide sion and enhance habitat for native d from the Mangatutu River	
Priority works for funding	Suggested works could be implemented either by an organisation or private citizens (using contractors or their own labour). This project could be undertaken as a whole, or in multiple smaller components.		
	 River erosion protection and remediation It is estimated from aerial photographs and on-the-ground knowledge that one third of this reach would require willow control. This equates to 7km of willow control at \$20 per metre (\$140,000). As 4km of the river is already being managed for erosion/habitat enhancement as part of a WRA/WRC funded project, there is 16km of river remaining that requires erosion management. This is likely to require hard (rock) and soft (vegetation) structures throughout at a cost of \$20,000 per km (16km = \$320,000). This would also provide approximately 10-15 fish habitat structures per km of stream. 		

	works should discuss this with council staff during project planning.	
	 Riparian fencing and planting Carry out riparian management along approximately 16km of the unmanaged section of stream (32km of streambank) with a minimum 5m setback from the top of the streambank. It is estimated that 46% of the unmanaged bank requires fencing. This equates to 14.7km of new fencing (5 wire, 2 electric) (\$117,760). It is estimated that approximately two thirds of the unmanaged stretch of 16km would require willow pole planting at 15m intervals. This would require 1422 poles (\$19,908). 	
	Native planting – 5m planted margin on both sides of the stream for 16km would require 16ha of native planting (\$600,832).	
	Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables	
	and miscellaneous professional fees. This is estimated to be 30% of the direct project costs.	
Time lag for benefits to be realised	If works were implemented at an even pace over a 7-year period, it is estimated that the majority of the project benefits would be seen within 1 year of project completion.	L = 7.5
Effectiveness of works	The Mangatutu Stream is in relatively good condition with some of the Vision & Strategy desired state aspects already being met, including being swimmable at times and fishable. It is expected that over the next 20 years there may be a slow deterioration in the stream in the absence of this project. Works included here address most of the threats to the feature and it is anticipated that if the project is fully completed then the stream will be in excellent condition and close to the Vision & Strategy state being achieved. The project does not address catchment land use, however the proposed fencing and planting works will assist in protecting and restoring water quality at this site.	W = 0.2
Risk of technical failure	There is a low to moderate risk of project failure due to technical feasibility if appropriately experienced practitioners are undertaking/advising on the more technical aspects of the project. Risks are mostly related to establishment of plantings or loss of works due to flooding. Techniques are well established and have been used	F = 0.9

,		г	
	previously on the Mangatutu Stream. River ero		
	structures should be designed by an appropriat	ely	
A da ata bilit	experienced practitioner.	A 0.22	
Adoptability	It is estimated that currently about a third of landowners		A = 0.32
	would adopt the works if they were fully incentivised. There		
	are large sections of stream that are meandering and erosive in nature and likely to flood on a regular basis. Landowners		
	may be unwilling to erect fences in these location		
	the potential maintenance costs. The extent of		
	setbacks may be a challenge in terms of uptake	-	
	there are some existing projects along this reac		
	provide a good example of what can be achieve		
	riparian margins.		
Information quality	Good – advice of local expert/s with a history o	fassociation	
	to the stream and experience in undertaking sin		
Knowledge gaps and	It is unknown specifically how much fencing alr		
response	and estimates are based on Waipā catchment r	•	
	surveys. This information would need to be col		
	early stages of the project. Specific locations fo		
	control structures would need to be determine preliminary site visits.	u during	
Socio-political risks	Moderate risk that the project will fail to meet	its goals over	P = 0.62
	the long term due to socio-political risks. Early	-	1 = 0.02
	engagement will be very important for the succ		
	delivery of this project.		
Project duration	7 years		
(years)			
Up-front cost – total			C = 1.56
for implementation phase/project	Task	Cost (\$)	
duration	River erosion protection/remediation (16km)	320,000	
	Willow management (7km)	140,000	
	Streambank fencing (14.7km)	117,760	
	Willow/poplar pole planting (1422 poles)	19,908	
	Native planting (16ha)	600,832	
	Project management/staffing/incidentals (30%)	359,550	
	Total	\$1,558,050	







Examples of large scale bank erosion along the Mangatutu River.



Examples of fish habitat enhancement.

WP 17	Waitomo River – headwaters to caves catchment	
Priority: Very high	erosion protection and remediation	BCR value
Relevant unit goal(s)	evant unit goal(s) The appropriate management of steep and erosion prone land is promoted and incentivised.	
	Water quality is such that waters within the catchment are swimmable and safe to take food from in all places.	
	Land uses are being adapted to match the capability of the land.	
Name of feature	Waitomo subcatchment and caves	
Brief description of feature	This 4434ha catchment is situated southwest of Ōtorohanga, upstream of Waitomo village, and contains the Waitomo Glowworm Caves.	
	Approximately 1394ha of land is LUC 6e or 7 in pasture and the catchment has been identified as a priority sediment catchment in the Waipā Catchment Plan. The pastoral land use is predominantly dairy support and dry stock with 10% of the catchment in plantation species, primarily pine. 36% of the catchment is in indigenous cover. The main waterway in this catchment is the Waitomo River.	
	This catchment has been the site of historic catchment management works, with the focus on protecting the Waitomo Glowworm Caves which were under significant threat from sedimentation. Issues, concerns and criticism peaked during the 1970s when sedimentation was at its worst and the future of the caves, ecologically and economically, was seriously threatened. Eventually through the work of the Waitomo Catchment Trust Board (who raised 65% of the cost of works) and Waikato Regional Council (who funded 35% of the cost of works) in the 1990s and 2000s, 118km of fencing was completed and 1223ha of erosion prone land retired in this catchment. Sediment monitoring in the river indicated that this led to a 40% reduction in sediment loads by the early 2000s. Recent monitoring indicates that loads may be starting to increase again. Further work is required in the catchment to prevent this.	
	Waikato Regional Council monitoring of water quality in the Waitomo Stream near the caves (Tumutumu Road) indicates that the stream is not safe for swimming due to high E. coli levels.	
Desired state to	- A subcatchment where land use matches capability.	
achieve the Vision & Strategy	 A stable stream network that has a fenced and well vegetated riparian margin along its entire length (at least 	

Impact on Vision & Strategy	 5m wide) to assign protection and fish species. River is swimman has access for respective to the main of th	VS = 200	
Key threats to the feature that this	Key threat	Impact on feature	
project addresses	Hill country erosion	Estimated to yield more than 2600 tonnes per year of sediment to the Waipā River.	
	E. coli to waterways	Impacts the swimmability of the site.	
Project goal/s		duction in suspended sediment in the tream within 10 years of project	
Priority works for funding	Suggested works of organisation or pro- own labour). This or in multiple sma Hill country soil con- 60ha LUC 6e m \$3000 per hect - 60ha LUC 6e m mānuka) at \$300 - 10km of fencing metre (8-wire and (Note: Estimates of on 10% of the land erosion risk. This due to the significon upper Waitomo and		
	 A flexible approact remaining erosion targeted to sedim 92ha LUC 7 ma mānuka) at \$30 19km of fencing wire and batter 		

	 3.6ha reducing sediment to waterways outside LUC class 6e, 7 and 8 land at \$5000 per hectare (e.g. dewatering, retiring seepages etc). Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees. 	
Time lag for benefits to be realised	This is estimated to be 25% of the direct project costs. If works were implemented at an even pace over a 10-year period it is estimated that the majority of the project benefits would be seen approximately one year after project completion.	L = 11
Effectiveness of works	 The Waitomo headwaters to caves subcatchment is generally in very good condition with many of the Vision & Strategy desired state aspects being met. It is expected that over the next 20 years there will be a slight deterioration in the condition of the catchment in the absence of this project. Works included here address some of the threats to the feature and it is anticipated that if the project is fully completed it would offset declines and make some progress towards achieving the Vision & Strategy state for water quality in 20 years' time. E. coli levels affecting swimmability of the stream should have some improvement as a result of this project, however will also need to be addressed through other mechanisms. The project does not directly address fish habitat and biodiversity threats however the proposed fencing and planting works provide secondary benefits to these values. 	W = 0.10
Risk of technical failure	There is a low risk of project failure due to technical feasibility. Risks are mostly related to establishment of plantings.	F = 0.87
Adoptability	It is estimated that about two thirds of landowners would adopt the works if they were fully incentivised. Uptake of management of LUC class 7 land may be more challenging however there is a well-established and successful catchment scheme already in place. This has provided an outstanding example of what can be achieved through this type of work.	A = 0.63
Information quality	Average – estimates are based on modelled information and input from catchment officers who are familiar with the subcatchment and are working with landowners to help them undertake similar works.	

Knowledge gaps and response	Estimates of LUC classes 6e and 7 come from a exercise. Farm scale information will need to b		
Socio-political risks	as part of this project. Very low risk that the project will fail to meet its goals over the long term due to socio-political risks.		P = 0.97
Project duration (years)	10 years		
Up-front cost – total			C = 1.54
for implementation	Task	Cost (\$)	
phase/project duration	Pole planting erosion prone LUC class 6e land (60ha)	180,000	
	Plantation species on erosion prone LUC class 6e land (60ha)	180,000	
	Fencing managed LUC class 6e land (10km)	200,000	
	Plantation species on LUC class 7 land (92ha)	276,000	
	Fencing managed LUC class 7 land (19km))	380,000	
	Treating erosion outside LUC class 6e, 7 and 8 land (3.6ha)	18,000	
	Project management/staffing/incidentals (25%)	308,500	
	Total	1,542,500	





A land slip above a Waitomo stream with soil conservation afforestation in the background.



Examples of landslips in the upper Waitomo catchment.



Sedimentation in the upper Waitomo catchment following heavy rain events



Example of fencing and retirement of erosion prone land in the upper Waitomo catchment.



Example of gully retirement and planting in the upper Waitomo catchment.

WP 18	Rehabilitation of fish habit	at at Ōtorohanga (Wainā	
Priority: High	River)		BCR value
Relevant unit goal(s)	There is a programme of restoration, enhancement and protection of pā tuna, other significant fishing sites and fish habitat without compromising the natural range of species.		
	Indigenous fish have access throughout the river catchments (except where natural barriers exist) and the catchment has an abundance of taonga species such as kōkopu, piharau, tuna, kōura and kāeo.		
Name of feature	The 1.3km section of Waipā Rive bridge and the weir	er between Ōtorohanga rail	
Brief description of feature	This section of Waipā River betw and the weir is approximately 1. Ōtorohanga flood protection sch either side. The river channel ha flood protection scheme and ma established along the banks for s	3km long. It is part of the neme and has flood levees on as been cleared as part of the atsudana willow trees	
	This area is historically significant to iwi with multiple historic pā and pakanga (battle) sites in the area. Ōtorohanga was previously a well inhabited papakāinga for many centuries.		
	This section of river has been identified by fish experts as having very little in-stream structure for fish habitat but with potential to provide a large area of habitat (particularly for tuna) if habitat rehabilitation work was undertaken.		
Desired state to achieve the Vision & Strategy	 The identified section of Waipā River has a healthy tuna population that utilise a network of in-stream structures for habitat. The identified section of river is swimmable, fishable and has 		
	 access for recreation. Iwi and communities have a strong connection to the river and are active in its use, protection and restoration. 		
Impact on Vision & Strategy	In a restored condition this section of the Waipā River at Ōtorohanga would have a very high impact on giving effect to the Vision & Strategy at a local level.		VS = 3
Key threats to the feature that this project addresses	Key threat Lack of in-stream woody debris and below water structures	Impact on the asset Reduction in cover and habitat for fish.	
Project goal/s	Within two years of the project section of Waipā River has adeq least 5 additional structures inst habitat for tuna.	uate in-stream structure (at alled per 500m) to provide	
Priority works for funding	It is not envisaged that this project be undertaken by private citizens but should be instead be undertaken by an organisation with expertise in river engineering and hydrology.		

	This work would need to be undertaken in consultation with Waikato Regional Council and Ōtorohanga District Council who manage the flood control scheme. Works must also consider risks to navigation safety as this stretch of the river is widely used for recreational boating and swimming.	
	Fish habitat structures This project involves the investigation, design and installation of 5 rock or wood structures per 500m (at least 13 structures in total) for the purpose of fish habitat rehabilitation. Design would need to account for the channel being a core component of the Ōtorohanga Flood Control Scheme.	
	A cost estimate of \$3700 per rock/woody habitat structure has been made. This includes investigation, design and installation of structures.	
	Resource consent Resource consent would be required and a cost estimate of \$7000 has been made. It is assumed that one consent would be applied for to authorise all of the structures.	
	Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees.	
	This is estimated to be 20% of the direct project costs.	
Time lag for benefits to be realised	If works were implemented at an even pace over a 2-year period, it is estimated that the majority of the project benefits would be seen upon project completion.	L = 2
Effectiveness of works	The Waipā River at Ōtorohanga is currently in moderate condition with some of the Vision & Strategy desired state aspects already being met, including being fishable and, at times, swimmable. There is not expected to be significant deterioration in the river over the next 20 years in the absence of this project. Works included here address only the threats to the feature's tuna fishery and it is anticipated that if the project is fully completed, the tuna habitat in this reach of the river will be in an improved condition. However, the project does not address catchment land use, water quality, biodiversity or other threats to the river.	W = 0.025
Technical feasibility	Risks are mostly related to loss of works due to flooding. There is a moderate risk of project failure due to technical feasibility. This can be minimised by works being undertaken in consultation with experiences practitioners.	F = 0.87

Adoptability	The land is owned by Ōtorohanga District Coun	cil and the	A = 1	
	channel is managed by Waikato Regional Cound			
	should be high support for adoptability so long	as these		
	organisations agree that there will be no impac	t on the		
		stability of the channel and the integrity of the flood control		
	scheme. This needs to be established in the ea			
-	project planning.			
Information quality	Good information – judgement of fish and river	management		
	experts with relevant local knowledge.			
Knowledge gaps and	The specific location and design of structures to			
response	needs to be determined during the early stages			
Socio-political risks	Low risk that the project will fail to meet its goals over the long		P = 0.85	
	term due to socio-political risks.			
Project duration (years)	2 years			
Up-front cost – total			C = 0.07	
for implementation	Task	Cost (\$)		
phase/project duration	Installation of structures for fish habitat (13)	48,100		
	Resource consent	7000		
	Project management/staffing/incidentals (20%)	11,020		
	Total 66,120			



DSCLAIMER While Wakato Regional Council has exercised all reasonable skill and care in controlling the contents of this information or its use by you.



The reach of the Waipā River where work is proposed.

WP 19	Waipā River bank erosion protection and remediation	
Priority: High	– Toa Bridge to Ōtorohanga	BCR value
Relevant unit goal(s)	River margins prone to significant erosion are managed to minimise erosion risk, whilst enhancing aquatic habitat and retaining the natural character of river systems.	
	Riparian planting of preferably indigenous species is undertaken to stabilise riverbanks, reduce erosion and enhance terrestrial and aquatic biodiversity.	
	Water quality is such that waters within the catchment are swimmable and safe to take food from in all places.	
Name of feature	Waipā River – Toa bridge to Ōtorohanga	
Brief description of feature	This reach consists of 21km of Waipā main stem from Toa bridge to Ōtorohanga. The river is steep through this stretch with a fall of 53m over 20km. This gradient is a contributing factor to the high risk of riverbank erosion through the reach. There is also a high incidence of flood driven erosion causing bank scouring. The river has a gravel bed and banks 3-4m high. Some erosion features in this stretch have been several hundred metres in length and 50m back into the bank. The river is fringed with crack willow and hybrid willow in places (the latter for erosion control). The river bed has been subject to extensive gravel extraction for commercial purposes. The river margin is fenced for a majority of the length but fences are periodically lost due to flooding. This area is historically significant to iwi with multiple historic pā and pakanga (battle) sites in the area. Ōtorohanga was previously a well inhabited papakāinga for many centuries. There are three marae with significant interests in this stretch of the Waipā.	
	Waikato Regional Council water quality monitoring indicates that the Waipā River at Ōtorohanga is sometimes safe for swimming, however E. coli levels make it regularly unsuitable.	
Desired state to achieve the Vision & Strategy	 A 21km stretch of river with stable, vegetated banks and where major erosion events are limited. A riparian margin that is well vegetated with native plants and exotic plants where required to prevent erosion. The river is swimmable, fishable and has access for recreation. Iwi and communities have a strong connection to the river and are active in its use, protection and restoration. 	
Impact on Vision & Strategy	In a restored condition the Waipā River – Toa bridge to Ōtorohanga – would have a high impact on giving effect to the Vision & Strategy at a Waipā catchment level.	VS = 80

Key threats to the			
feature that this	Key threat	Impact on feature	
project addresses	Mass bank erosion events and ongoing bank scouring	Estimated to yield approximately 2293 tonnes of sediment per year to the Waipā River, excluding	
		major flood events.	
Project goal/s	 Within 10 years of project commencement: The river has stable banks and a continuous vegetated (native and exotic for erosion control) 21km margin from Toa's bridge to Ōtorohanga. There is 100% stock exclusion with at least 10m riparian setbacks. Sediment to the Waipā River over this stretch is reduced by 15%. 		
Priority works for funding	organisation or private	be implemented either by an citizens (using contractors or their ect could be undertaken as a whole, omponents.	
	 erosion control structures would be cost of \$22,500 each and vegetation and ovegetation, poles) ar willow removal whe Note: Waikato Region for this type of work should be consulted It is estimated that 4 required in total beh setbacks. This is equ (\$150,208). A further 8km of veg and willow removal/ erosion control is est \$40 per metre of rive be replaced with hybrid 	on and remediation 0 sites along this stretch would need ctures/treatment. On average these 150m long and with an estimated a. Structures should be a mix of rock costs include materials (rock, nd contracted services (including for re required). Total cost \$450,000. along this stretch of the river and prior to any works being planned. km of native planting would be ind these structures with 10m lates to 4ha of native planting etation management (aged poplar management) for the purposes of timated to be required at a cost of er. (\$320,000). This vegetation should orid willow at 10 m intervals (for 16km s equates to 1600 poles (\$22,400).	
	protection structures, i earthworks associated resource consent from Integrated Catchment consent for much of th therefore anyone prop	w removal, installation of erosion nstallation of woody debris and any with these actions may require Waikato Regional Council. Council's Management division hold an existing is type on work on this waterway and osing to undertake river management his with council staff during project	

	 Riparian Fencing & Planting 6.5km of the 21km stretch is currently being managed as part of the WRA/WRC funded Waipā Rerenoa project. This leaves 14.5km of river (29km of bank) unmanaged. Based on surveys of Waipā catchment waterways, it is estimated that 46% of the remaining unmanaged riverbank will still require fencing. This equates to 13.3km of fencing. Fence should be set back 10m from the river and be minimum 3 wire electric (\$74,480). It is estimated that 13ha of native planting will be required along newly fenced margins (\$488,176). 	
	Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees.	
	This is estimated to be 30% of the direct project costs.	
Time lag for benefits to be realised	If works were implemented at an even pace over a 10-year period, it is estimated that the majority of the project benefits would be seen approximately 7 years after project commencement.	L = 7
Effectiveness of works	The Waipā River – Toa bridge to Ōtorohanga – is currently in moderate condition with some of the Vision & Strategy desired state aspects already being met, including being fishable and on occasion swimmable. It is expected that over the next 20 years there will be some deterioration in the river along this stretch in the absence of this project. Works included here focus on the threats to the feature's banks but would have secondary benefits on nutrient attenuation and fish habitat. It is anticipated that if the project is fully completed, the stability of the riverbanks in this reach will be in significantly improved condition and close to the Vision & Strategy state being achieved in 20 years' time. However the project does not fully address catchment land use, water quality or biodiversity threats and it is acknowledged that achieving the overall Vision & Strategy at this site will take longer than the 20-year time frame of the Restoration Strategy.	W = 0.05
Risk of technical failure	There is a moderate risk of project failure due to technical feasibility. Risks are related to establishment of plantings or loss of works due to flooding and/or erosion before they are established; and vegetation removal exacerbating erosion along this stretch. Exotic vegetation in and along waterways reduces flow velocities. Therefore it will be very important that willow removal is staged over the 10 years of the	F = 0.87

	project and followed by replanting with native species to reduce the rate of channel modification resulting from increased flows. Risks would be further minimised by the fencing setbacks being at least 10m and by planting sterile willow poles to stabilise banks while native plantings establish. River erosion structures should be designed by an appropriately qualified practitioner.		
Adoptability	It is estimated that about half of landowners would adopt the works if they were fully incentivised. There are large sections of river that are meandering and erosive in nature and likely to flood on a regular basis. Landowners may be unwilling to erect fences in these locations due to the potential maintenance costs. Fencing setbacks of at least 10m from the riverbank should help to minimise this, however this loss of grazing land may also be a challenge with uptake, as has been the case with similar river margin projects. It would be beneficial to establish that sites that demonstrate the benefits of stable, vegetated river margins.		A = 0.54
Information quality	Good information – advice of local expert/s with a history of association with this reach of the river and experience in undertaking similar work locally.		
Knowledge gaps and response	It is unknown exactly how much fencing already exists and estimates are based on Waipā catchment riparian surveys and local knowledge. This would need to be establish during project planning.		
Socio-political risks	Moderate risk that the project will fail to meet its goals over the long term due to socio-political risks. Early stakeholder engagement will be very important for the successful delivery of this project.		P = 0.62
Project duration (years)	10 years		
Up-front cost – total			C = 1.96
for implementation phase/project	Task	Cost (\$)	
duration	Erosion protection structures (21km)	450,000	
	Native planting behind structures (4ha)	150,208	
	Willow management (8km)	320,000	
	Poplar/willow pole planting (1600)	22,400	
	Fencing (13.3km)	74,480	
	Native planting behind new fences (13ha)	488,176	
	Project management/staffing/incidentals (30%)	451,579	
	Total	\$1,956,843	





Examples of major bank erosion and instability along the Waipā River – Toa's bridge to Ōtorohanga.



A stretch of Waipā River – Toa's bridge to Ōtorohanga – where there was significant bank erosion (above) that has been remedied and stabilised (bottom photo).



Before and after river erosion remediation and stabilisation works along the Waipā River – Toa's bridge to Ōtorohanga



Examples of rock and vegetation erosion protection structures (as proposed as part of this project).

WP 20	Upper Pūniu catchment erosion protection and	
Priority: Medium	remediation	BCR value
Relevant unit goal(s)	The appropriate management of steep and erosion prone land is promoted and incentivised.	
	Water quality is such that waters within the catchment are swimmable and safe to take food from in all places.	
	Land uses are being adapted to match the capability of the land.	
Name of feature	The Upper Puniū subcatchment	
Brief description of feature	The Upper Puniū is a 16,857ha catchment situated southeast of Te Awamutu and bordering the eastern edge of the Waipā catchment. Approximately 7357ha of land is LUC 6e or 7 in pasture and the catchment has been identified as a priority sediment catchment in the Waipā Catchment Plan. The land use is a mixture of dairy, dairy support and dry stock with small areas of woodlot forestry, primarily pine (2% of the catchment). 24% of the catchment is in indigenous cover.	
	The area is of tribal significance to Maniapoto and Waikato, known as Mangatoatoa, the same name held by the marae situated directly at the confluence of the Puniū and Waipā rivers. Better management of the upper catchment would improve the historic and cultural relationship of the marae and its people with the natural resources. It would also enhance the ability of the marae to sustain its people and manuwhiri (visitors) with local kai (food).	
	The main waterways in this catchment are the Puniū River, Waipāri Stream and Mangakomua Stream.	
Desired state to achieve the Vision & Strategy	 A subcatchment where land use matches capability and where the waterways have a riparian margin that is well vegetated with native plants and at least 5m wide. Waterways are swimmable, fishable and have access where appropriate for recreation. Iwi and community have a strong connection to the catchment and its waterways and are active in their use, protection and restoration. 	
Impact on Vision & Strategy	In a restored condition the Upper Puniū catchment would have a very high impact on giving effect to the Vision & Strategy at a Waipā catchment level.	VS = 200
Key threats to the feature that this	Key threat Impact on feature	
project addresses	Hill country Estimated to yield more than 3400 tonnes of erosion sediment per year to the Waipā River.	
Project goal/s	There is a 25% reduction in suspended sediment in the Puniū River within 15 years of project commencement.	

Priority works for	Suggested works could be implemented either by an		
, funding	organisation or private citizens (using contractors or their own		
-	labour). This project could be undertaken as a whole, or in		
	multiple smaller components.		
	Hill country soil conservation		
	 - 688ha LUC 6e managed with open space pole planting at \$3000 per hectare (\$2,064,000). 		
	 - 688ha LUC 6e managed with plantation species (pine or mānuka) at \$3000 per hectare (\$2,064,000). 		
	 - 116km of fencing the managed LUC 6e land at \$20 per metre (8-wire and batten) (\$2,320,000). 		
	 - 1857ha LUC 7 managed with plantation species (pine or mānuka) at \$3000 per hectare (\$5,571,000). 		
	 - 172km of fencing the managed LUC 7 land at \$20 per metre (\$3,440,000). 		
	 - 52ha reducing sediment to waterways outside LUC class 6e, 7 and 8 land at \$5000 per ha (e.g. dewatering, retiring 		
	 seepages etc.) (\$260,000). - 74 hunter days per year for 3 years of goat control while plantings on 6e and 7 establish. Control carried out over a 7400ha eree 		
	7400ha area. - 34km fencing existing indigenous vegetation at \$25 per metre (\$850,000).		
	Project management/staffing/incidentals		
	Staff to carry out landowner liaison, iwi engagement, Health		
	and Safety requirements, negotiate agreements, inspect works,		
	manage parts of the work as required (e.g. fencing or planting),		
	project reporting and financial management. Incidentals include transport, office overheads, consumables and		
	miscellaneous professional fees.		
	This is estimated to be 30% of the direct project costs.		
Time lag for benefits to be realised	If works were implemented at an even pace over a 20-year period, it is estimated that the majority of the project benefits would be seen approximately 16 years after project commencement.	L = 16	
Effectiveness of	The upper Puniū subcatchment is in moderate to poor	W = 0.25	
works	condition when compared to desired state, with few of the	vv – 0.23	
WOLKS	Vision & Strategy aspirations being met. It is expected that over		
	the next 20 years there may be a deterioration in the condition		
	of the catchment in the absence of this project. It is		
	acknowledged that achieving the Vision & Strategy desired		
	state will take longer than the 20-year horizon used for the		
	purposes of the Restoration Strategy. However, works included		
	in this project address some of the key threats to the feature		
	and it is anticipated that if the project is fully completed the		
	upper Puniū subcatchment will be significantly closer to the		
	Vision & Strategy desired state in 20 years' time, particularly		
	when it comes to land use matching capability being swimmable. The project does not direct	•	
---	--	--------------	-----------
	fish habitat and biodiversity, however improve expected as secondary benefits.		
Risk of technical failure	Risks are mostly related to establishment of pla works due to severe erosion before they are es is a high risk of project failure due to technical	F = 0.82	
Adoptability	It is estimated that about 20% of landowners w works if they were fully incentivised. Uptake o LUC class 6e and 7 land may be low and we are significant similar works being undertaken in th date. Early community engagement, flexibility identifying key farmers will be very important f this project.	A = 0.2	
Information quality	Average – estimates are based on modelled inf input from catchment officers who are familiar subcatchment.		
Knowledge gaps and response	Estimates of LUC classes 6e, 7 and 8 come from exercise. Farm scale information will need to b part of this project.		
Socio-political risks	Low risk that the project will fail to meet its go term due to socio-political risks.	P = 0.85	
Project duration (years)	20 years		
Up-front cost – total for implementation			C = 21.66
phase/project	Task	Cost (\$)	
duration	Pole planting erosion prone LUC class 6e land (688ha)	2,064,000	
	Plantation species on erosion prone LUC class 6e land (688ha)	2,064,000	
	Fencing managed LUC class 6e land (116km)	2,320,000	
	Plantation species on erosion prone LUC class 7 land (1857ha)	5,571,000	
	Fencing managed LUC class 7 land (172km)	3,440,000	
	Treating erosion outside LUC class 6e, 7 and 8 (52ha)	260,000	
	Fencing indigenous forest remnants (34km)	850,000	
	Goat control on treated 6e and 7	90,576	
	Project management/staffing/incidentals (30%)	4,997,872	
	Total	\$21,657,448	



DISCLAIMER: While Waikato Regional Council has exercised all reasonable skill and care in avviance (whether direct, indirect or consequential) arising out of the provision of this information of the second secon

WP 21	Mangapū River erosion protection and riparian	
Priority: High	enhancement	
Relevant unit goal(s)		
	Riparian planting of preferably indigenous species is undertaken to stabilise riverbanks, reduce erosion and enhance terrestrial and aquatic biodiversity.	
	Water quality is such that waters within the catchment are swimmable and safe to take food from in all places.	
Name of feature	Mangapū River	
Brief description of feature	This is a 35km stretch of river broken up into two reaches. The top reach (Waitomo Valley Road to Trooper Road) is 21km long. Approximately 8km of this has already been managed and fenced/planted. This leaves 13km unmanaged in this reach. This reach is part of an alluvial river flat. Banks have a relatively small amount of stabilising vegetation and are subject to slumping following high flow flood events. The lower reach (downstream of Waitomo Valley Road) is 14km of stream. This portion is largely unmanaged (from a riparian perspective) and requires bank stabilisation as the river is incising through this reach. The Mangapū River is historically and culturally significant to Ngāti Maniapoto. There are historic forts along the Mangapū established during intertribal wars including Pukehōkio, Pānikau	
	and Te Tuhi-o-te-ao-mārama. This was a commonly traversed area. There are 14 marae with interests in the Mangapū River. According the water quality monitoring undertaken regularly by Waikato Regional Council, the Mangapū River at Ōtorohanga is not safe for swimming due to unsatisfactory levels of E. coli, and the river's water clarity is unsatisfactory.	
Desired state to achieve the Vision & Strategy	 A 35km reach of river with stable, vegetated banks and where major erosion events are limited. A riparian margin that is fenced to exclude stock with a minimum 5m setback, and that is well vegetated with native plants and exotic plants where required to prevent erosion. Native fish are abundant and there is a wide diversity of species present The river is swimmable, fishable, safe for gathering kai, and has access for recreation. Iwi and communities have a strong connection to the river and are active in its use, protection and restoration. 	
Impact on Vision & Strategy	In a restored condition the Mangapū River would have a high impact on giving effect to the Vision & Strategy at a Waipā catchment level.	VS = 80

Key threats to the feature that this	Key threat	Impact on feature	
project addresses	Riverbank erosion	Estimated to yield approximately 2600 tonnes of sediment per year to the Waipā River, excluding major flood events.	
	Stock access to the stream	Reduced water quality and destruction of riparian vegetation.	
	Lack of riparian cover and associated fish habitat	Reduced habitat for adult fish.	
Project goal/s	vegetated with a minimu	ngapū River is stable, fenced and um 5m margin along its entire length le, shelter and food for native fish.	
Priority works for funding	Suggested works could be i or private citizens (using co	mplemented either by an organisation ntractors or their own labour). This n as a whole, or in multiple smaller	
	 requires willow removal. control at \$20 per metree As 8km of the top reach as part of an existing probank) remaining in the to This is likely to require so at approximately 1 struct (13km is \$32,500). The loc require a mix of soft and structures. Estimated 2 (14km is \$70,000). The top reach is estimated of the riverbank length (spacing equates to 866 p estimated to require pol riverbank (14km of river to 933 poles (\$13,062). Activities such as willow rep protection structures, instate earthworks associated with consent from Waikato Regi Catchment Management d much of this type on work 	by imately 15% of the lower reach This equates to 5.25km of willow (\$105,000). of the river is already being managed ject, there is 13km of river (26km op reach that requires management. oft (vegetation) structures throughout ture per km (a cost of \$2500 per km) ower 14km stretch of the river would small hard engineering structures per km (\$5000 per km) ed to require pole planting along half 13km of riverbank). Poles at 15m poles (\$12,124). The lower stretch is e planting along two thirds of the bank). Poles at 15m spacing equates moval, installation of erosion llation of woody debris and any these actions may require resource onal Council. Council's Integrated ivision hold an existing consent for on this waterway and therefore take river management works should	

	 Riparian fencing and planting The top 13km of the river (26km of bank) unmanaged is estimated to require 46% of riverbank to be fenced with a 5-wire, 2-electric (12km of fencing) (\$96,000). The lower 14km of the river (28km of bank) is estimated to require 46% of riverbank to be fenced (13km of fencing (\$104,000). Fence should be set 5m back from the top of the bank and adjoining wetland areas included in the fencing. A 5-metre planted margin on both sides of the river for 25km would require 27ha of native planting (\$938,800) Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees. This is estimated to be 25% of the direct project costs.	
Time lag for benefits to be realised	If works were implemented at an even pace over an eight year period, it is estimated that the majority of the project benefits would be seen approximately two years after project completion.	L = 10
Effectiveness of works	The Mangapū is currently in poor to moderate condition when compared to desired state, with few of the Vision & Strategy aspirations being met. The river is not swimmable year-round or 100% excluded from stock access. However, it still retains important values and the river is of high cultural significance for iwi. It is expected that over the next 20 years there may be some deterioration in the river in the absence of this project. Works included here focus on the threats to the feature's banks but would have secondary benefits of nutrient attenuation, reducing E. coli to waterways and improving fish habitat. It is anticipated that if the project is fully completed, the stability of the riverbanks in this reach will be in significantly improved condition and progress will be made towards the Vision & Strategy desired state. However, the project does not fully address catchment land use, water quality or biodiversity elements, and additional work outside the scope of this project would be required for the river to be swimmable.	W = 0.05
Risk of technical failure	Low risk of project failure due to technical feasibility. Risks are mostly related to establishment of plantings or loss of works due to flooding.	F = 0.9
Adoptability	It is estimated that approximately half of the landowners would adopt the works if they were fully incentivised. The extent of the fencing setbacks may provide some challenge in terms of uptake, and some landowners may be concerned about maintenance of fences following floods. However, this should be minimised once plantings mature and there are significant existing works along	A = 0.54

	the Mangapū that provide a good example of	what can be	
	achieved with larger riparian margins.		
Information quality	Average – estimates are based on aerial photographs, Waipā catchment riparian surveys and input from catchment officers		
	who are familiar with the reach and are working with landowners to help them undertake similar works.		
Knowledge gaps and response	It is unknown specifically how much fencing already exists and how close it is to the stream edge. Detailed fencing requirements would need to be determined in the early stages of the project.		
Socio-political risks	Very low risk that the project will fail to meet its goals over the long term due to socio-political risks.		P = 0.97
Project duration (years)	8 years		
Up-front cost –			C = 1.7
total for	Task	Cost (\$)	
implementation phase/project duration	River erosion management and protection (27km)	102,500	
	Willow management (5.25ha)	105,000	
	Fencing (25km)	200,000	
	Willow/poplar pole planting (1799 poles)	25,186	
	Native planting (25ha)	938,800	
	Project management/staffing/incidentals (25%)	342,871	
	Total	\$1,714,357	

Legend





Ōtorohai

Pohatuiri

Waitomo Village

Mangapū River erosion protection and riparian enhancement

WWRRS Project Map

Created by: Tane Desmond Projection: NZTM Date: December 2017

Status: Final Request No.: N/A File name: WWRRS.gws

Hangatiki

Te Kuiti

0.00 0.75 1.50 2.25 3.00 3.75 Kilometers KIIOTTIETETS
 Waikato Regional Aerial Photography Service (WRAPS) 2012. Imagery sourced from Waikato Regional
 Council. Licensed under CC BY 3.0 NZ.
 Waikato Regional Council 2013-2013. Application Activity (IRIS) Data. Licensed under CC BY 3.0 NZ.
 Waikato Regional Council 2013-2013. Application Activity (IRIS) Data. Licensed under CC BY 3.0 NZ.
 Waikato Regional Council 2004-2012. WRC REEC Catchment/ Watercourse/ Watershed.
 Data derived from NIVA, MRL (LINZ - Copyright Reserved. Licensed under CC BY 3.0 NZ.
 Digital Boundary Data sourced from Statistics New Zealand.
 "150.000 Hydrodogical data sourced from LINZ. Crown Copyright Reserved."
 Topographic Maps sourced from LINZ. Crown Copyright Reserved.
 Wikikato Regional Council 2004-2014. Urban - Rural Boundaries. Licensed under CC BY 3.0 NZ.
 Liandcover Database 4 reproduced with the permission of Landcare Reserved. We Zealand Limited.
 Licensed under CC BY 3.0 NZ.
 content of this information. Waikato Regional Council accepts na labity in canticat. List or sthewase howstower, for any fors, damage, piper o

Scale 1:100,000@A4 Portrait

Waikato REGIONAL COUNCIL

A4

DISCLAIMER: While Waikato Regional Council has exercised all reasonable skill and care in c avviance (whether direct, indirect or consequential) arising out of the provision of this informatic



Mangapū River showing devegetated banks and lack of adequate setback.

WP 22	Biodiversity restoration within lowland kahikatea	
Priority: Very high	fragments in the Mangapū catchment	BCR value
Relevant unit goal(s)	The catchment has an interconnected network of healthy, indigenous ecosystem types (forest, shrubland, wetlands, lakes, river and stream habitats and margins) supporting native flora and fauna.	
Name of feature	Lowland kahikatea remnants in Waipā catchment and their associated wetlands	
Brief description of feature	Within the Waipā catchment only 2.07% of the conifer- dominated forests (kahikatea) remain (approximately 170ha). Fifty hectares of these are within the Mangapū River catchment and the rest spread throughout the remainder of the Waipā River catchment. Of the 50ha within the Mangapū catchment there is an 18.5ha area known as the Pehitawa Kahikatea Forest Reserve. This site currently has a management plan in place and has almost virgin condition forest with mature pole-stand kahikatea, some around 120 years old.	
	Most other stands are small (less than 10ha), fragmented and impacted by stock, land drainage and plant and animal pests. They require further management to ensure their existence long term. There is also potential to extend existing stands by undertaking further planting.	
	The Mangapū River is historically and culturally significant to Ngāti Maniapoto. There are historic forts along the Mangapū established during intertribal wars including Pukehōkio, Paanikau and Te Tuhi-o-te-ao-mārama. This was a commonly traversed area. There are 14 marae with interests in the Mangapū River.	
Desired state to achieve the Vision & Strategy	 Lowland kahikatea remnants and associated wetlands are fenced to exclude stock, densely vegetated with native vegetation and connected to riparian corridors when they are located nearby. Native plant regeneration occurs naturally within the native bush remnants and any existing black mudfish populations within their associated wetland areas are retained. 	
Impact on Vision & Strategy	In a restored condition the kahikatea forest remnants in the Mangapū catchment would have a very high impact on giving effect to the Vision & Strategy at a local level.	VS = 18

Key threats to the			
feature that this	Key threat	Impact on the feature	
project addresses	Further fragmentation of forest fragments	Affects the viability of the forest fragment through increasing edge effects, increasing potential for weed and animal pest invasion. Also reduces the habitat available for native species.	
	Stock access to native forest fragments	Stock prevent native regeneration and open up areas to plant pests.	
	Lack of riparian vegetation and stock access to riparian areas	Reduction in in-stream biodiversity.	
Project goal/s	Mangapū catchment are to the other forest remna areas as identified. - Native planting is underta	ect commencing: remnants identified within the fenced to exclude stock and connected ants, associated wetlands and riparian aken (along with weed control) to fill where there is no native vegetation.	
Priority works for funding	or private citizens (using co	implemented either by an organisation ontractors or their own labour). This en as a whole, or in multiple smaller	
	lowland kahikatea remnan Reserve) and 35ha of adjoi areas. The total area of the	pration work consists of 50ha of ts (including 18.5ha Pehitawa Forest ning riparian margins and wetland e site is 85ha. Recommended work punt management already being prest Reserve.	
	Pehitawa Forest Reserve. vegetation types, detailed and costs. The estimated of Further investigation is req fencing, planting and week	d be developed for the areas outside of This should involve a site survey of recommended management actions cost for a management plan is \$10,000. Juired to determine the amount of d control required. However, based on owing estimates and assumptions have	
	fencing/fence upgrade w estimated cost of \$8 per - Four hectares of native p	15.6km perimeter of the site requires ith a 5 wire (2 electric) fence at an	

	 General weed control using a knapsack sprayer required over another 10% (7ha) of the site for a period of 3 years at an estimated cost of \$2800 per hectare per year (\$58,800). Possum control across the full 85ha area for a period of 3 years until native plantings are established, at \$600 per hectare x 85ha (\$51,000). Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees. 	
	This is estimated to be 20% of the direct project costs.	
Time lag for benefits to be realised	If works were implemented at an even pace over a five year period, it is estimated that the majority of the project benefit would be seen soon after project completion.	L = 5.5
Effectiveness of works	The lowland kahikatea remnants in Waipā catchment and their associated wetlands are currently in moderate to good condition with some of the Vision & Strategy desired state aspects already being partially met. Condition is expected to slightly decline over the next 20 years in the absence of this project. However, if this project is successfully completed then these features are expected to improve and be closer to desired state in 20 years' time, with aspects related to stock exclusion and native revegetation being addressed.	W = 0.1
Risk of technical failure	Low risk of project failure due to technical feasibility. Risk is mostly related to the potential for invasive weeds to overtake native planting at the site and potential for flooding to damage nearby fencing and planting.	F = 0.87
Adoptability	It is conservatively estimated that approximately 60% of landowners would adopt the works if they were fully incentivised. Land tenure is a mix of iwi owned, private and charitable trust.	A = 0.6
Information quality	Poor – management requirements based solely on aerial photography.	
Knowledge gaps and response	Detailed fencing, planting and pest control requirements would need to be determined during project planning.	
Socio-political risks	Very low risk that the project will fail to meet its goals due to socio-political risks	P = 0.97
Project duration (years)	5 years	

Up-front cost – total	t – total		C = 0.41
for implementation phase/project duration	Task	Cost (\$)	
	Management plan	10,000	
	Fencing (15.6km)	64,400	
	Native planting (4ha)	158,208	
	Weed control	58,800	
	Possum control	51,000	
	Project Management/staffing/incidentals (20%)	68,482	
	Total	410,890	



Created by: Tane Desmond Status: Final Projection: NZTM Request No.: N/A Date: December 2017 File name:WWRRS.gws © Waikato Regional Council 2013-2015. Application Activity (IRIS) Data. Licensed under CC BY 3.0 NZ. This Data may be subject to the Privacy Act. © Waikato Regional Council 2004-2014. Urban - Rural Boundaries. Licensed under CC BY 3.0 NZ. © Waikato Regional Council 2004-2012, WRC REC Catchment/ Watercourse. Topographic Maps sourced from LINZ. Crown Copyright Reserved. Watershed. Data derived from NIWA, MfE, LINZ – Copyright Reserved. Licensed under CC BY 3.0 NZ. *1:50,000 Hydrological data sourced from NZTopo Database. Crown Copyright Reserved.

Digital Boundary Data sourced from Statistics New Zealand.



DSCLAIMER: While Waikato Regional Council has exercised all reasonable skill and care in controlling the contents of this information, Waikato Regional Council accepts no liability in contract, tort or otherwise howsoever, for any loss, damage, injury or expense (whether direct, indirect or consequential) arising out of the provision of this information or its use by you.



Kahikatea forest fragments in the Mangapū River catchment.

WP 23	Mangaokewa Stream erosion protection and remediation	
Priority: High	Mangaokewa Stream erosion protection and remediation	BCR value
Relevant unit goal(s)	River margins prone to significant erosion are managed to minimise erosion risk, whilst enhancing aquatic habitat and retaining the natural character of river systems.	
	Riparian planting of preferably indigenous species is undertaken to stabilise riverbanks, reduce erosion and enhance terrestrial and aquatic biodiversity.	
	Water quality is such that waters within the catchment are swimmable and safe to take food from in all places.	
Name of feature	Mangaokewa Stream	
Brief description of feature	A 23km reach of stream which flows from the Viaduct Reserve through the Te Kūiti township to the confluence with the Mangapū River at Hangatiki. The stream is relatively incised in places with steep banks that are susceptible to slumping. Approximately 6.6km of the stream lies within the township. Te Araroa walkway follows alongside the upper Mangaokewa from the viaduct reserve to the Te Kūiti township. There is native planting and erosion control associated with this pathway.	
	There has been flood control works undertaken on the river through the urban area of Te Kūiti to reduce the risk of the township flooding. This included the creation of a larger floodway. Any works within this reach would need an assessment undertaken on the impact on flood levels and flood control infrastructure. There has been isolated catchment and river management works undertaken to address streambank erosion at ad hoc sites throughout the reach. There has been some privately funded fencing and native planting along this reach of stream. This extends for about 1km of bank.	
	Waikato Regional Council monitoring of the Mangaokewa Stream at Te Kūiti indicates that the stream is not swimmable due to unsatisfactory levels of E. coli, and has unsatisfactory water clarity. The Maniapoto Maori Trust Board has recently developed a Cultural Health Index (CHI) for this river.	
Desired state to achieve the Vision & Strategy	 A 23km stretch of river with stable, vegetated banks and where major erosion events are limited. A riparian margin that is fenced to exclude stock with a minimum 5m setback, and is well vegetated with native plants and exotic plants where required to prevent erosion. Native fish are abundant and there is a wide diversity of species present The river is swimmable, fishable, safe for gathering kai, and has access for recreation. 	

Impact on Vision & Strategy	are active in its use, protection and restoration. In a restored condition the Mangaokewa Stream would have a very high impact on giving effect to the Vision & Strategy at a local level.		VS = 12
Key threats to the feature that this	Kov throat limnact on teature		
project addresses	Riverbank erosion	Estimated to yield approximately 2700 tonnes of sediment per year to the Waipā River, excluding major flood events.	
	Stock access to the river	Reduced water quality and trampling of banks and destruction of riparian vegetation.	
	De-vegetated banks	Bank slumping and increased sediment to water.	
Project goal/s	 Within 10 years of project commencement: A 23km reach of the Mangaokewa River is stable, fenced (5m setback) and vegetated along its entire length providing increased shade, shelter and food for native fish. Stock is 100% excluded from the Mangaokewa River. 		
Priority works for funding	or private citizens (using c	implemented either by an organisation ontractors or their own labour). This en as a whole, or in multiple smaller	
	 (vegetation) structures (\$5000 per km) (\$115,0 Based on aerial photogr the reach it is estimated 	m of stream is likely to require soft throughout at a frequency of 2 per km 00). Taphs and on-the-ground knowledge of that approximately 15% (or 3.5km) of require willow/poplar management at a 570,000).	
	protection structures, inst earthworks associated wit consent from Waikato Reg Catchment Management of much of this type on work anyone proposing to unde	emoval, installation of erosion allation of woody debris and any h these actions may require resource gional Council. Council's Integrated division hold an existing consent for on this waterway and therefore rtake river management works should aff during project planning.	
	with a 5-wire (2 electric	ting of the streambank will require fencing) fence. This equates to 21.2km of . This should have a minimum of a 5m	

		1
	 setback from the top of the bank and include adjoining wetland areas. Riparian planting should be a mix of native species with exotics where required for stability. It is estimated that willow/poplar poles would be required at 15m intervals over 23km of streambank length (1533 poles is \$21,462). Native planting should be a 5m margin on both sides of the stream for 21.2km of bank length, so 10.6ha (\$398,051). Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees. 	
	This is estimated to be 25% of the direct project costs.	
Time lag for benefits	If works were implemented at an even pace over a 10-year	L = 11
to be realised	period, it is estimated that the majority of the project benefits	
	would be seen approximately one year after project completion.	
Effectiveness of	The Mangaokewa Stream is currently in poor to moderate	W = 0.15
works	condition with few of the Vision & Strategy desired state aspects	
	being met. The stream is not swimmable and stock still have	
	access in places. However, the Mangaokewa still retains	
	important values and is of high cultural significance for iwi. It is	
	expected that over the next 20 years there may be some deterioration in the river in the absence of this project. Works	
	included here focus on the threats to the feature's banks but	
	would have secondary benefits of reducing E. coli to water,	
	nutrient attenuation and improving fish habitat. It is anticipated	
	that if the project is fully completed, the stability of the	
	riverbanks in this reach will be in significantly improved condition	
	and progress will be made towards the Vision & Strategy state	
	being achieved in 20 years' time. The project does not fully	
	address catchment land use, water quality or biodiversity threats.	
Risk of technical	There is a low risk of project failure due to technical feasibility if	F = 0.9
failure	appropriately experienced practitioners are undertaking/advising	
	on the more technical aspects of the project. Risks are mostly	
	related to establishment of plantings or loss of works due to	
	flooding. Techniques are well established and have been used	
	previously on other local streams. River erosion structures	
Adaptability	should be designed by an appropriately qualified practitioner.	A = 0 F 4
Adoptability	It is estimated that at least half of landowners would adopt the works if they were fully incentivised. The extent of the fencing	A = 0.54
	setbacks may provide some challenge in terms of uptake, and	
	some landowners may be concerned about maintenance of	
	fences following floods. However, this should be minimised once	
	plantings mature. There are limited examples of this type of	
L		I

Project duration (years)	term due to socio-political risks. 10 years		
(years) Up-front cost – total			C = 0.98
for implementation	Task	Cost (\$)	
phase/project duration	River erosion management and protection	115,000	
	Willow/poplar management (3.5km)	70,000	
	Willow/poplar disposal	14,000	
	Fencing (21.2km)	169,000	
	Willow/poplar pole planting (1533 poles)	21,462	
	Native planting (10.6ha)	398,051	
	Project management/staffing/incidentals (25%)	196,878	





Mangaokewa Stream during a small flood showing unstable banks and limited riparian margins.

			1	
WP 24	Mangarapa			
Priority: Medium		BCR value		
Relevant unit goal(s)	The appropriate m land is promoted a			
		uch that waters within the catchment are after to take food from in all places.		
		ng adapted to match the capability of the		
Nous offerstung				
Name of feature				
Brief description of feature	east of Te Kūiti. A in pasture and the sediment catchme use is a mixture of small areas of woo primarily pine. Ap indigenous cover.	Mangarapa subcatchment A 5306ha catchment situated to the south of Ōtorohanga and east of Te Kūiti. Approximately 2678ha of land is LUC 6e or 7 in pasture and the catchment has been identified as a priority sediment catchment in the Waipā Catchment Plan. The land use is a mixture of dairy, dairy support and dry stock with small areas of woodlot forestry (2% of the catchment), primarily pine. Approximately 8% of the catchment is in indigenous cover. The main waterway in this catchment is the Mangarapa Stream.		
	whenua for many kākahu (clothing)	ea provided natural resources to tāngata purposes including rongoā (medicine), and kai (food). An historic village, named Te confluence of the Mangarapa and		
Desired state to achieve the Vision & Strategy	 A subcatchmen where the streat vegetated with The stream is sw appropriate for Iwi and commu catchment and protection and 			
Impact on Vision & Strategy	In a restored cond have a high impac a Waipā catchmer	VS = 100		
Key threats to the feature that this	Key threat	Impact on feature		
project addresses	Hill country erosion	Estimated to yield more than 3400 tonnes of sediment per year to the Waipā River		
Project goal/s	There is a 25% rec Mangarapa Strear commencement.			
Priority works for	Suggested works could be implemented either by an			
funding	organisation or private citizens (using contractors or their			

	Ι	
	own labour). This project could be undertaken as a whole, or in multiple smaller components.	
	 Hill country soil conservation 325ha LUC 6e managed with open space pole planting at \$3000 per hectare (\$975,000). 325ha LUC 6e managed with plantation species (pine or mānuka) at \$3000 per hectare (\$975,000). 54km of fencing the managed LUC 6e land at \$20 per metre (8-wire and batten) (\$1,080,000). 78ha LUC 7 managed with plantation species (pine or mānuka) at \$3000 per hectare (\$234,000). 78ha LUC 7 managed LUC 7 land at \$20 per metre (8-wire and batten) (\$280,000). 14km of fencing managed LUC 7 land at \$20 per metre (8-wire and batten) (\$280,000). 18.5ha reducing sediment to waterways outside LUC class 6e, 7 and 8 land at \$5000 per ha (e.g. dewatering, retiring seepages etc) (\$92,500). 14.5km fencing existing indigenous vegetation at \$25 per metre (8-wire and batten) (\$362,500). 27 hunter days per year for 3 years of goat control while plantings on 6e and 7 establish. Control carried out over a 	
	2700ha area. Project management/staffing/incidentals	
	Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees.	
	This is estimated to be 25% of the direct project costs.	
Time lag for benefits to be realised	If works were implemented at an even pace over a 15-year period, it is estimated that the majority of the project benefits would be seen approximately 13-14 years after project commencement.	L = 18
Effectiveness of works	The Mangarapa subcatchment is in moderate to poor condition when compared to desired state, with few of the Vision & Strategy aspirations being met. It is expected that over the next 20 years there may be a deterioration in the condition of the catchment in the absence of this project. It is acknowledged that achieving the Vision & Strategy desired state will take longer than the 20 year horizon used for the purposes of the Restoration Strategy. However, works included in this project address some of the key threats to the feature and it is anticipated that if the project is fully completed it would offset anticipated decline and make some headway with respect to achieving the Vision & Strategy state in 20 years' time. The project does not directly address all threats to the Mangarapa, however the proposed fencing and	W = 0.2

	planting works would provide secondary benefi E. coli to waterways and improving fish habitat biodiversity.		
Risk of technical failure	Risks are mostly related to establishment of pla of works due to severe erosion before they are However, proposed management actions are w accepted for managing hill country erosion. Th moderate risk of project failure due to technica	F = 0.87	
Adoptability	It is estimated that about 20% of landowners w the works if they were fully incentivised. Uptak management of LUC class 6e and 7 land may be are not aware of significant similar works being this catchment to date. Early community engage identifying key farmers will be very important for of this project.	A = 0.2	
Information quality Knowledge gaps and	Average – estimates are based on modelled info input from catchment officers who are familiar subcatchment. Estimates of LUC classes 6e, 7 and 8 come from	with the	
response	exercise. Farm scale information will need to b part of this project.	•	
Socio-political risks	Low risk that the project will fail to meet its goa long term due to socio-political risks.	P = 0.85	
Project duration (years)	15 years		
Up-front cost – total			C = 5.19
for implementation phase/project	Task	Cost (\$)	
duration	Pole planting erosion prone LUC class 6e land (325ha)	975,000	
	Plantation species on erosion prone LUC class 6e land (325ha)	975,000	
	Fencing managed LUC class 6e land (54km)	1,080,000	
	Plantation species on erosion prone LUC class 7 land (78ha)	234,000	
	Fencing managed LUC class 7 land (14km)	280,000	
	Erosion outside LUC class 6e, 7 and 8 land (18.5ha)	53,600	
	Fencing indigenous forest bordering LUC class 6e land (14.5km)	362,500	
	Goat control on treated LUC class 6e and 7 land	33,048	
	Project management/staffing/incidentals (25%)	998,287	
	Total	\$4,991,435	





Examples of general topography of the Mangarapa catchment.



Mass movement and slips.



Examples of erosion protection pole planting, above, and areas of plantation species, below (from the Mangapū/Mangaokewa catchments).

Mangatea cat	chment erosion protection and remediation		
		BCR value	
	The appropriate management of steep and erosion prone land is promoted and incentivised.		
Land uses are b	eing adapted to match the capability of the land.		
Mangatea subc	atchment		
subcatchment s land is LUC 6e of identified as a p Catchment Plan support and dry primarily pine (indigenous cove	southwest of Te Kūiti. Approximately 615ha of or 7 in pasture and the catchment has been priority sediment catchment in the Waipā n. The land use is a mixture of dairy, dairy y stock with small areas of woodlot forestry, 1% of catchment). 7% of the catchment is in er. The main waterway in this catchment is the		
There are two r	narae situated alongside the Mangatea stream.		
 Waterways w stock with a mative plants erosion. Native fish ar species prese The river is sy has access fo Iwi and command are active 	with a riparian margin that is fenced to exclude minimum 5m setback, and is well vegetated with and exotic plants where required to prevent re abundant and there is a wide diversity of ent. wimmable, fishable, safe for gathering kai, and or recreation. munities have a strong connection to the river e in its use, protection and restoration.		
high impact on		VS = 15	
	Impact on feature		
Hill country erosion	Estimated to yield more than 2600 tonnes per year of sediment to the Waipā River.		
	-		
Suggested work organisation or			
	The appropriate promoted and i Water quality is swimmable and Land uses are b Mangatea subc A 1326ha catch subcatchment s land is LUC 6e c identified as a p Catchment Plan support and dry primarily pine (indigenous cove Mangatea Streat There are two r - A subcatchm - Waterways v stock with a r native plants erosion. - Native fish an species prese - The river is sy has access fo - Iwi and comr and are active In a restored co high impact on level. Key threat Hill country erosion There is a 25% r	promoted and incentivised.Water quality is such that waters within the catchment are swimmable and safe to take food from in all places.Land uses are being adapted to match the capability of the land.Mangatea subcatchmentA 1326ha catchment situated in the upper Mangapū subcatchment southwest of Te Kūiti. Approximately 615ha of land is LUC 6e or 7 in pasture and the catchment has been identified as a priority sediment catchment in the Waipā Catchment Plan. The land use is a mixture of dairy, dairy support and dry stock with small areas of woodlot forestry, primarily pine (1% of catchment). 7% of the catchment is in indigenous cover. The main waterway in this catchment is the Mangatea Stream.There are two marae situated alongside the Mangatea stream.• A subcatchment where land use matches capability.• Waterways with a riparian margin that is fenced to exclude stock with a minimum 5m setback, and is well vegetated with native plants and exotic plants where required to prevent erosion.• Native fish are abundant and there is a wide diversity of species present.• The river is swimmable, fishable, safe for gathering kai, and has access for recreation.• Iwi and communities have a strong connection to the river and are active in its use, protection and restoration.In a restored condition the Mangatea Stream would have a very high impact on giving effect to the Vision & Strategy at a local level.Key threatImpact on feature Hill countryHill countryEstimated to yield more than 2600 tonnes	

	Hill country soil conservation	
	- 76ha LUC 6e managed with open space pole planting at	
	\$3000 per hectare (\$228,000).	
	- 76ha LUC 6e managed with plantation species (pine or	
	mānuka) at \$3000 per hectare (\$228,000).	
	- 14km of fencing the managed LUC 6e land at \$20 per metre	
	(8-wire and batten) (\$280,000).	
	 - 5ha LUC 7 managed with plantation species (pine or mānuka) at \$3000 per hectare (\$15,000). 	
	 2km of fencing the managed LUC 7 land at \$20 per metre (8- wire and batten) (\$40,000). 	
	- 12.4ha reducing sediment to waterways outside LUC class 6e,	
	7 and 8 land at \$5000 per hectare (e.g. dewatering, retiring	
	seepages etc.) (\$62,000).	
	- 6 hunter days per year for 3 years of goat control while	
	plantings on LUC 6e and 7 land establish. Control carried out	
	over a 600ha area.	
	- 3.4km fencing existing indigenous vegetation at \$25 per	
	metre (8-wire and batten) (\$85,000).	
	Project management/staffing/incidentals	
	Staff to carry out landowner liaison, iwi engagement, Health and	
	Safety requirements, negotiate agreements, inspect works,	
	manage parts of the work as required (e.g. fencing or planting),	
	project reporting and financial management. Incidentals include	
	transport, office overheads, consumables and miscellaneous	
	professional fees.	
	This is estimated to be 25% of the direct project costs.	
Time lag for benefits	If works were implemented at an even pace over a 10-year	L = 11
to be realised	period, it is estimated that the majority of the project benefits	
	would be seen approximately one year after project completion.	
Effectiveness of	The Mangatea subcatchment is in poor to moderate condition	W = 0.275
works	with some of the Vision & Strategy desired state aspects being	
	met. It is expected that over the next 20 years there may be a	
	deterioration in the condition of the catchment in the absence	
	of this project. It is acknowledged that achieving the Vision &	
	Strategy desired state will take longer than the 20 year horizon	
	used for the purposes of the Restoration Strategy. However,	
	works included in this project address some of the key threats to	
	the feature and it is anticipated that if the project is fully	
	completed it would offset anticipated decline and make some	
	headway with respect to achieving the Vision & Strategy state in	
	20 years' time. The project does not directly address all threats	
	to the Mangatea, however the proposed fencing and planting	
	works would provide secondary benefits to reducing E. coli to	
Risk of technical	waterways and improving fish habitat and biodiversity.	F = 0.82
	There is a moderate risk of project failure due to technical	Γ - υ.δΖ
failure	feasibility. Risks are mostly related to establishment of	
	plantings or loss of works due to flooding.	

Adoptability	It is estimated that about a quarter of landowners would adopt the works if they were fully incentivised. Uptake of management of LUC class 6e and 7 land may be low and we are not aware of significant similar works being undertaken in this catchment to date. Early community engagement and identifying key farmers will be very important for the success of this project.		
Information quality	Average – based on modelled information and knowledge.	local expert	
Knowledge gaps and response	Estimates of LUC classes 6e, 7 and 8 come from exercise. Farm scale information will need to b part of this project.	•	
Socio-political risks	Low risk that the project will fail to meet its goa term due to socio-political risks.	als over the long	P = 0.85
Project duration (years)	10 years		
Up-front cost – total		(A)	C = 1.18
for implementation phase/project	Task	Cost (\$)	
duration	Pole planting erosion prone LUC class 6e land (76ha)	228,000	
	Plantation species on erosion prone LUC class 6e land (76ha)	228,000	
	Fencing managed LUC class 6e land (14km)	280,000	
	Plantation species on erosion prone LUC class 7 land (5ha)	15,000	
	Fencing managed LUC class 7 land (2km)	40,000	
	Erosion outside LUC class 6e, 7 and 8 land (12.4ha)	62,000	
	Fencing indigenous forest remnants 3.4km)	85,000	
	Goat control on treated LUC class 6e and 7 land	7344	
	Project management/staffing/incidentals (25%)	236,336	
	Total	\$1,181,680	



DSCLAIMER: While Wakato Regional Council has exercised all reasonable skill and care in controling the contents of this information, Waikato Regional Council accepts no liability in contract, fort or otherwise howsoever, for any loss, damage, injury or expense (whether direct, indirect or consequential) ansing out of the provision of this information or its up you.



Shallow soil slip (rear), mass land movement (middle) and stabilisation poplar planting (foreground),

WP 26	Mangar	ama catchment erosion protection and		
Priority: Medium		BCR value		
Relevant unit goal(s)	The appropriate promoted and i			
		s such that waters within the catchment are d safe to take food from in all places.		
	Land uses are b			
Name of feature	Mangarama Ca	tchment		
Brief description of feature	adjacent to the the Waipā catc or 7 in pasture priority sedime land use is a mi small areas of v catchment). Ap	Mangarama CatchmentA 5439ha catchment situated southwest of Te Kūiti. This is adjacent to the Mangatea catchment in the southwest corner of the Waipā catchment. Approximately 2428ha of land is LUC 6e or 7 in pasture and the catchment has been identified as a priority sediment catchment in the Waipā Catchment Plan. The land use is a mixture of dairy, dairy support and dry stock with small areas of woodlot forestry, primarily pine (1.5% of the catchment). Approximately 6% of the catchment is in indigenous cover.		
	The main wate	rway in this catchment is the Mangarama Stream.		
Desired state to achieve the Vision & Strategy	 The main waterway in this catchment is the Mangarama Stream. A subcatchment where land use matches capability and waterways have a riparian margin that is fenced with a minimum 5m setback to exclude stock, and is vegetated with native plants and exotic plants where required to prevent erosion. Native fish are abundant and there is a wide diversity of species present The river is swimmable, fishable, safe for gathering kai, and has access for recreation. Iwi and communities have a strong connection to the river and are active in its use, protection and restoration. 			
Impact on Vision & Strategy		ondition the Mangarama subcatchment would h impact on giving effect to the Vision & Strategy	VS = 25	
Key threats to the feature that this	Key threat	Impact on feature		
project addresses	Hill country erosion	Estimated to yield approximately 3200 tonnes of sediment per year to the Waipā River.		
Project goal/s		There is a 25% reduction in suspended sediment in the Mangarama Stream within 15 years of project commencement.		
Priority works for funding	Suggested work organisation or labour). This pr multiple smalle			

	 Hill country soil conservation 264ha LUC 6e managed with open space pole planting at \$3000 per hectare (\$792,000) 264ha LUC 6e managed with plantation species (pine or mānuka) at \$3000 per hectare (\$792,000) 42km of fencing managed LUC 6e land at \$20 per metre (8- wire and batten) (\$840,000) 315ha LUC 7 managed with plantation species (pine or mānuka) at \$3000 per hectare (\$945,000) 31km of fencing managed LUC 7 land at \$20 per metre (8- wire and batten) (\$620,000) 31.ha reducing sediment to waterways outside LUC class 6e, 7 and 8 land at \$5000 per hectare (e.g. dewatering, retiring seepages etc) (\$15,500) 25 hunter days per year for 3 years of goat control while plantings on LUC class 6e and 7 land establish. Control carried out over a 2500ha area. 6.2km fencing existing indigenous vegetation at \$25 per metre (8-wire and batten) (\$155,000) Staff to carry out landowner liaison, iwi engagement, Health and Safety requirements, negotiate agreements, inspect works, manage parts of the work as required (e.g. fencing or planting), project reporting and financial management. Incidentals include transport, office overheads, consumables and miscellaneous professional fees. 	
Time lag for benefits to be realised	This is estimated to be 25% of the direct project costs. If works were implemented at an even pace over a 15-year period, it is estimated that the majority of the project benefits	L = 13.5
Effectiveness of works	would be seen approximately 14 years after the project began. The Mangarama subcatchment is in poor to moderate condition with some of the Vision & Strategy desired state aspects being met. It is expected that over the next 20 years there may be a deterioration in the condition of the catchment in the absence of this project. It is acknowledged that achieving the Vision & Strategy desired state will take longer than the 20 year horizon used for the purposes of the Restoration Strategy. However, works included in this project address some of the key threats to the feature and it is anticipated that if the project is fully completed it would offset anticipated decline and make some headway with respect to achieving the Vision & Strategy state in 20 years' time. The project does not directly address all threats to the Mangarama, however the proposed fencing and planting works would provide secondary benefits of reducing E. coli to waterways and improving fish habitat and biodiversity.	W = 0.3
Risk of technical failure	There is a moderate risk of project failure due to technical feasibility. Risks are mostly related to establishment of plantings or loss of works due to flooding or erosion.	F = 0.82

Adoptability	It is estimated that about a quarter of landowners would adopt the works if they were fully incentivised. Uptake of management of LUC class 6e and 7 land may be low and we are not aware of significant similar works being undertaken recently in this catchment. Early community engagement, flexibility of approach and identifying key farmers will be very important for the success of this project.		
Information quality	Average – based on modelled information and l knowledge.	ocal expert	
Knowledge gaps and response	Estimates of LUC classes 6e, 7 and 8 come from exercise. Farm scale information will need to b part of this project.	•	
Socio-political risks	There is a low risk that the project will fail to me the long term due to socio-political risks.	eet its goals over	P = 0.85
Project duration (years)	15 years		
Up-front cost – total for implementation	Task	Cost (\$)	C = 5.45
phase/project duration	Pole planting erosion prone LUC class 6e land (264ha)	Cost (\$) 792,000	
	Plantation species on erosion prone LUC class 6e land (264ha)	792,000	
	Fencing managed LUC class 6e land (42km)	840,000	
	Plantation species on erosion prone LUC class 7 land (315ha)	945,000	
	Fencing managed LUC class 7 land (31km)	620,000	
	Erosion outside LUC class 6e, 7 and 8 land (3.1ha)	15,500	
	Fencing indigenous forest remnants (6.2km)	155,000	
	Goat control on treated LUC class 6e and 7 land	30,600	
	Project management, staffing/incidentals (25%)	1,047,525	
	Total	5,237,625	



DISCLAIMER: While Wakato Regional Council has exercised all reasonable skill and care in controling the contents of this information, Wakato Regional Council accepts no liability in contract, for or otherwise howsoever, for any loss, damage, injury or expense (whether direct, indirect or consequential) ansing out of the provision of this information or its use by you.



An example of the type of erosion common in the Mangarama catchment.



An example of the type of works proposed for this project – afforestation and pole planting for soil stabilisation.

WP 27	Biodiversity restoration of priority sites in the upper	
Priority: High	Waipā catchment	BCR value
Relevant unit goal(s)	The catchment has an interconnected network of healthy, indigenous ecosystem types (forest, shrubland, wetlands, lakes, river and stream habitats and margins) supporting native flora and fauna.	
	Where possible, the natural functioning of floodplains and other ephemeral wetland sites is restored and maintained.	
	Wetlands are created or protected and actively managed to enhance multiple functions.	
Name of feature	Upper Waipā River forest remnants, wetlands and associated tributary streams.	
Brief description of feature	A range of biodiversity sites in the upper Waipā River catchment in the vicinity of the Rangitoto Range. Sites include 1054ha of forest remnants, 380ha wetland/riparian site and a 1.7km long tributary waterway.	
	Land ownership is predominantly private with the exception of the 247ha size Otoru Scenic Reserve and Pekepeke Wetland (Waipā Myers) area, both of which are owned by Department of Conservation.	
	The upper Waipā is of high significance to iwi and its marae as it holds water of the highest quality, generally used for the most important ceremonies. The puna (springs) of the upper Waipā flow to the main stem, forming and shaping the rest of the catchment area and sustaining the many marae along its banks.	
	Sites included here have been identified as being within the top 30% of terrestrial biodiversity sites within the Waikato catchment because of their terrestrial biodiversity values and representativeness of this ecosystem type. One exception to this is the Waipā tributary stream which has been identified as within the top 40% of waterway sites for biodiversity.	
Desired state to achieve the Vision & Strategy	 Forest remnants and wetlands adjacent to the upper Waipā River are densely vegetated with native plant species, connected to riparian corridors and protected from stock grazing. Native plant regeneration occurs naturally within the forest remnants. Iwi and communities have a strong connection to the sites and are active in their use, protection and restoration. 	
Impact on Vision & Strategy	In a restored condition, the upper Waipā River adjacent forest remnants, wetlands and associated tributary streams would	VS = 30

	have a high impact on Waipā catchment leve	giving effect to the Vision & Strategy at a I.	
Key threats to the feature that this	Key threat	Impact on the feature	
project addresses	Further fragmentation of forest fragments	Affects the viability of the forest fragment through increasing edge effects, increasing potential for weed and animal pest invasion. Also reduces the habitat available for native species.	
	Stock access to native forest fragments	Stock prevent native regeneration and open up areas to plant pests.	
	Lack of riparian vegetation and stock access to riparian areas	Water quality impacts and reduction in in in-stream biodiversity.	
	Pest willow trees	Shade out native vegetation.	
Priority works for funding	 Within 6 years of the project commencing: Forest remnants and wetlands identified are fully fenced to exclude stock. The Waipā River tributary waterway identified is fenced to exclude stock with a minimum 5 wire (2 electric) fence and a riparian margin at least 5m wide. Native planting (and associated weed control) is carried out within the riparian margin at 1.5m spacing. The waterway flowing from Waipā Myers wetland is free from willow pests and has a naturally regenerating native riparian margin. Suggested works could be implemented either by an 		
	labour). This project c multiple smaller comp Further investigation i amount of fencing and required. However, b knowledge the follow made:	e citizens (using contractors or their own ould be undertaken as a whole, or in onents. is required to determine the exact d planting and weed control ased on aerial photographs and local ing estimates and assumptions have been e and adjoining forest fragment – 2km of	
	 post and batten fend Other forest remnar required at \$20 per Waipā River tributar wire fencing (2 wire metre (\$9,600); 0.75 a cost of \$37,552 pe purchase, planting la The waterway flowir 	cing required at \$20 per metre (\$40,000). hts – 18km of post and batten fencing	

	based willow control along its margins (\$4000 per hectare is \$6000) plus a further two to three years of followup treatment at \$2000 per hectare (\$6000).		
	Project management/staffing/incidentals Staff to carry out landowner liaison, iwi engageme and Safety requirements, negotiate agreements, ir manage parts of the work as required (e.g. fencing project reporting and financial management. Incid include transport, office overheads, consumables a miscellaneous professional fees.	nspect works, or planting), lentals	
	This is estimated to be 20% of the direct project costs.		
Time lag for benefits to be realised	If works were implemented at an even pace over a 5-year period, it is estimated that the majority of the project benefits would be seen within 1 year of project completion.		L = 5.5
Effectiveness of works	The upper Waipā River adjacent forest remnants, wetlands and associated tributary streams are currently in very good condition with some of the Vision & Strategy desired state aspects already being met, including being accessible in some circumstances and the streams and wetlands swimmable and fishable. Condition is not expected to significantly decline or improve over the next 20 years in the absence of this project. However, if this project is successfully completed then these sites are expected to be in very good condition and closer to desired state in 20 years' time, with aspects related to stock exclusion and native revegetation being addressed.		W = 0.025
Risk of technical failure	Risks are mostly related to establishment of plantings. There is a low risk of project failure due to technical feasibility.		F = 0.92
Adoptability	It is estimated that about two thirds of landowners would adopt the works if they were fully incentivised.		A = 0.65
Information quality	Good information – advice of local expert/s with a history of association to selected sites.		
Knowledge gaps and response	Further investigation is required to determine the specific quantities of fencing and planting required. This should be undertaken during the early stages of project planning.		
Socio-political risks	Very low risk that the project will fail to meet its goals over the long term due to socio-political risks.		P = 0.97
Project duration (years)	5 years		
Up-front cost – total for implementation	Task	Cost (\$)	C = 0.54
phase/project	Fencing (21.2km)	409,600	
duration	Native planting (0.75ha)	28,164	
	Ground based willow control	12,000	
	Project Management/staffing/incidentals (20%)	89,953	
	Total	539,717	





DISCLAIMER: While Wakato Regional Council has exercised all reasonable skill and care in controling the contents of this information. Waikato Regional Council accepts no liability in contract, tort or otherwise howsoever, for any loss, damage, injury or expense (whether direct, indirect or consequential) ansing out of the provision of this information or its use by you.



An example of forest remnants in the upper Waipā.